

7-14

6 040921

API NUMBER 15-163-22275-00-02

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

165' W C, SEC. 17, T 9 S, R 18 W/E
NW NE

_____ feet from S section line
_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4678

Lease Name Hilgers B Well # 8

Operator: Lasmø
Name & Address: Box 1365
Great Bend, Ks. 67530

County Rooks 114.79

Well Total Depth 3532 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 259 w/165

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ U&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cement License Number _____

Address Russell, Ks.

Company to plug at: Hour: 8:30AM Day: 14 Month: July Year: 19 88

Plugging proposal received from Millard Kelso

(company name) Kelso Casing (phone) _____

were: Ordered 250 sks 65/35 Poz 10% Gel 2% Lite add w/1/4# F.C. plus 6 sks Hulls.

RECEIVED
STATE CORPORATION COMMISSION

SEP 16 1988
9-16-88
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30AM Day: 14 Month: July Year: 19 88

ACTUAL PLUGGING REPORT 5 1/2" set at 3531' w/125 sks. Top perf at OH'. Plugged

bottom 3475', w/sand and 5 sks cement to 3450'. Shot pipe one time and recovered 2049'.

Pumped in 8 5/8" 250 sks cement w/1/4# F.C. plus 6 sks Hulls mixed in cement. Max 500#

S.I. 300#.

Remarks: _____

(If additional description is necessary, use BACK of this form.)

INVOICED
observe this plugging.

DATE 9-20-88

Signed Dennis L. Hamel
(TECHNICIAN)
Dennis L. Hamel

INV. NO. 22308