

4-041862

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

12-12

API Number: 15-163-22,120-00-00

NW SE NE /4 SEC. 17, 09 S, 18 W  
3630 feet from S section line  
990 feet from E section line

Operator license# 3456

Lease: Hilgers "B" Well # 6

Operator: AFG Energy, Inc.

County: Rooks 114.88

Address: P.O. Box 458  
Hays, Kansas 67601

Well total depth 3535 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 267 feet  
w/ 180 sxs.cmt.

Aband. oil well , Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD \_\_\_\_\_, D & A \_\_\_\_\_

Plugging contractor: Allied Cementing, Inc. License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00 A.M. Day: 13 Month: December Year 1996

Plugging proposal received from: Terry W. Piesker

Company: AFG Energy, Inc. Phone: 913-625-6374

Were: 5 1/2" casing set at 3530' w/150 sxs.  
Perfs. at 3482' - 3486' - 3306' - 3311' - 3269' - 3273' - 3249' - 3252'. O.H. 3530' - 3535'.  
Ordered 300 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.  
D.V. at 1361' with 300 sxs cement circulate.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[ ], Part[ X ], None[ ]

Completed: Hour: 11:15 A.M., Day: 13, Month: December, Year: 1996

Actual plugging report: Ran tubing 3516' - spotted 140 sxs 60/40 pozmix - 10% gel with 300# hulls. Pulled tubing to 1507' - spotted 130 sxs 60/40 pozmix - 10% gel with 200# hulls circulated cement at surface. Pulled tubing and squeezed 25 sxs cement. Max. P.S.I. 700#. S.I.P. 500#. 8 5/8" - pressured-up 700#.

Remarks: Allied Cementing.  
Condition of casing (in hole): GOOD \_\_\_\_\_ BAD \_\_\_\_\_ Anhy. plug: YES  NO \_\_\_\_\_  
Bottom plug (in place): YES , CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES , NO \_\_\_\_\_  
Plugged through TUBING \_\_\_\_\_, CASING \_\_\_\_\_ Elevation: 2082 K.B.

I did / did not observe the plugging.

Dennis L. Hamel  
(agent)

INVOICED  
DATE DEC 31 1996  
INV. NO. 47186