

6 041291

4-9

328

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-163-03360-00-00

W/2 SE NW, SEC. 17, T 9 S, R 18 W/Ex

3300 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5635

Lease Name Stahl Well # 3

Operator: The Gene Brown Co.

County Rooks 102.08

Name & Address Drawer 220

Well Total Depth 3141 feet

Plainville, Ks. 67663

Conductor Pipe: Size feet

Surface Casing: Size 10 feet 240 sks cwc.

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton Cementing License Number

Address Hays, Ks.

Company to plug at: Hour: 8:00 AM Day: 9 Month: April Year: 19 91

Plugging proposal received from Tom Brown

(company name) Gene Brown Co. (phone)

were: 5 1/2 casing set at 3530 w/NA sks cement: O.H. to 3541; Perf anhy at 1500.

Perf base dakota at 900. Ordered 300 sks 65/35 poz 8% gel w/1/4 lb f.c. plus

500 lbs. hulls.

Plugging Proposal Received by Dennis Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 11:15AM Day: 9 Month: April Year: 19 91

ACTUAL PLUGGING REPORT Pumped in 5 1/2 casing w/25 sks cement w/1/4 lb f.c. plus pumped in add 225 sks cement w/1/4 lb f.c. and 400 lbs. hulls mixed in cement.

Max 800 lbs. S.I. 300 lbs. Pumped in 10" casing w/50 sks cement w/1/4 lb f.c. and 100 lbs. hulls mixed in cement. Max 900 lbs. S.I. 300 lbs.

STATE CORPORATION COMMISSION

4-22-91  
APR 22 1991

Remarks: (if additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 4-29-91

INV. NO. 31707

Signed Dennis L Hamel (TECHNICIAN)

Dennis L. Hamel