

12-23

To: 6 040998
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163-03358-00-00

C S/2 NE NWSEC. 17, T 9 S, R 18 W/E
_____ feet from S section line
_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5058

Lease Name Stahl Well # 1

Operator: Griggs Oil Inc.
Name & Address 107 N. Market S. 800
Wichita, Ks. 67202

County _____ Rooks 114.76
Well Total Depth 3531 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 252' w/150

Abandoned Oil Well Gas Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cement License Number _____

Address Russell, Ks.

Company to plug at: Hour: 9:00 AM Day: 23 Month: Dec Year: 19 88

Plugging proposal received from Wilbur Berg

(company name) Griggs Oil (phone) _____

were: 5 1/2" casing set at 3524' w/125 sks. Top perf at 3304'. Perf anhy at 1500' and base dakota at 875'. Top of fish (tubing and rods) 1675': Top of fluid 1040'. Ordered 250 sks 65/35 Poz 10% Gel 2% Lite w/1/4# F.C. plus 6 sks Hulls.

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:00PM Day: 23 Month: Dec Year: 19 88

ACTUAL PLUGGING REPORT Pumped in 5 1/2" casing 150 sks cement w/1/4# F.C. plus sks

Hulls mixed in cement. Max 600# S.I. 500# psi. Pumped in 8 5/8" casing 50 sks cement w/1/4# F.C. plus 2 sks Hulls mixed in cement. Max 600# S.I. 500# psi.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED
I do not intend to serve this plugging.

DATE 1-19-87
INV. NO. 23 700

Feb 5

Signed Dennis L. Hamel (TECHNICIAN)

Dennis L. Hamel