

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-21676-00-00
Spot: NESESE Sec/Twnshp/Rge: 28-26S-13W
990 feet from S Section Line, 330 feet from E Section Line
Lease Name: STRAIT Well #: 11
County: PRATT Total Vertical Depth: 4515 feet

Operator License No.: 9232
Op Name: TIMBERLINE OIL & GAS CORPORATIO
Address: 4000 PENROSE PLACE
RAPID CITY, SD 57702

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4514	2080	WITH 250 SX CMT
SURF	13.38	331		WITH 350 SX CMT

\$ 146,74

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/09/2007 9:15 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: FELIX TOBAR Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3770' & 5 SX CMT. PLUG AT 800' WITH 10 SX GEL & 50 SX CMT. PLUG AT 360' WITH 100 SX CMT. PLUG AT 40' WITH 40 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/09/2007 10:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 3770' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 5 1/2" CASING. 1ST PLUG AT 800' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 360' WITH 100 SX CMT. 3RD PLUG AT 40' WITH 40 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4473	4479		
4458	4466		
4211	4236		
3980	3984		
3944	3948		
3821	3825		

INVOICED
DATE 1-24-07
INV. NO. 2007061238

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND.

Plugged through: CSG

District: 01



Signed

Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED

JAN 19 2007

KCC WICHITA

Form SP-2/3

[Handwritten signature]