

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-21610-00-01
Spot: NESESE Sec/Twnshp/Rge: 27-26S-11W
675 feet from S Section Line, 468 feet from E Section Line
Lease Name: VERNON Well #: 1
County: PRATT Total Vertical Depth: 4660 feet

Operator License No.: 31629
Op Name: NASH OIL & GAS, INC.
Address: P. O. BOX 8747
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4432		WITH 5 SX CMT
PROD	4.5	4471	0	
SURF	8.625	425		

\$ 151.45

Well Type: SWD UIC Docket No: D27195.0 Date/Time to Plug: 11/27/2006 10:30 AM
Plug Co. License No.: 32983 Plug Co. Name: STEVE'S WELL SERVICE, INC.
Proposal Rcvd. from: JERRY NASH Company: NASH OIL & GAS Phone: (620) 672-3800

Proposed Plugging Method: CIBP PLUS 5 SX CMT. PLUG AT 1500' WITH 50 SX CMT. PLUG AT 640' CIRCULATE CMT TO SURFACE OR PLUG AT 630' WITH 50 SX CMT, PLUG AT 450' WITH 50 SX CMT, PLUG AT 60-0' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/27/2006 2:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

HOLES IN 4 1/2" CASING FROM 2660-640'. POSSIBLE CASING LEAKS HIGHER THEN 640'. DIDN'T HUNT FOR HOLES ANY HIGHER THAN 640'. SET CIBP @ 4432' & PUT 5 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. RUN TUBING INTO 1500'. 1ST PLUG AT 1500' WITH 50 SX CMT. 2ND PLUG AT 620'. CIRCULATED CMT INSIDE 2 3/8" TUBING/4 1/2" CASING ANNULUS & 4 1/2" CASING/8 5/8" SURFACE PIPE ANNULUS BACK TO SURFACE WITH 350 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4471	4660	OH	
4288	4292		DUALY COMP. P

Remarks: USED 60/40 POZMIX 6% GEL BY JET STAR.

Plugged through: TBG

INVOICED
DATE 1-24-07
INV. NO. 2007061236

District: 01



Signed

Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 18 2007

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

PJT