


STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.



Locate well correctly on above
Section Plat

Rocks..... County. Sec. 5, Twp. 9S, Rge. 18, X20
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. 1660' from south line, 330' from west line, SW, NW, SW
Lease Owner..... Gulf Oil Corporation
Lease Name..... E. Hilgers Well No. 1
Office Address..... Box 661, Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole)..... Dry Hole
Date well completed..... December 9 1947
Application for plugging filed..... December 9 1947
Application for plugging approved..... December 9 1947
Plugging commenced..... December 10 1947
Plugging completed..... December 10 1947
Reason for abandonment of well or producing formation..... Dry Hole

If a producing well is abandoned, date of last production..... None 19.....
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced?..... Yes

Name of Conservation Agent who supervised plugging of this well.....
Producing formation..... Arbuckle Depth to top..... 3554' Bottom..... 3584' Total Depth of Well..... 3584 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				13-3/8"	37'	None
				8-5/8"	1468'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from..... feet to..... feet for each plug set.

Filled hole with heavy mud from 3584' to 1450'. Dumped
15 sacks of cement at 1450'. Filled hole with heavy mud
to 200'. Dumped 15 sacks of cement at 200'. Dumped heavy
mud to 30'. Filled hole with 10 sacks of cement to base
of cellar.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Mr. A. M. Bell, Jr. - General Superintendent
Address..... Box 661
Tulsa, Oklahoma


STATE OF Kansas, COUNTY OF Rice, ss.
H. H. Wright (employee of owner) or ~~owner~~ of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-
described well as filed and that the same are true and correct. So help me God.

(Signature).....
Box 544, Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of December, 1947.

My commission expires..... May 18, 1950

Notary Public.



21-6858-RS 2-47-6M

Received
12/17/47

WELL LOG OF WILMERS #1

Spudding date: 11/25/47
 Date casing set: 11/26/47
 Date rotary completed: 12/9/47
 Date cable completed:

Location:
 Section 8, Twp. 26, Rge. 18W,
 DeKalb County, Kansas

TOTAL DEPTH 3284'

FROM	TO	FORMATION	REMARKS
0	56	Soil and sand	For 1 ft. of 12-5/8" casing, but at 20'5" with 18 in. casing.
56	125	Sand	
125	210	Shale	
210	700	Shale and shells	
700	950	Shale and sand	
950	1185	Sand	
1185	1440	Shale and shells	
1440	1480	Shale	
1480	1495	Anhydrite	
1495	1980	Shale	
1980	2000	Lime	
2000	2225	Shale and lime	
2225	2515	Sand and shale	
2515	2700	Lime	
2700	2800	Lime and shale	
2800	2822	Lime	
2822	2841	Shale and lime	
2841	2855	Compensated	
2855	2884	Artificial lime	
2884		TOTAL DEPTH	

Subscribed and sworn to before me this
 19th day of December, 1947.

I certify the above and foregoing to be
 a true and exact copy of the original
 driller's log of the Wilmers #1 well.

Eric Stenger
 Notary Public.
 My commission expires 2/28/51.

C. J. Moore

Received
 12/22/47
 DEC 22 1947

