

15-163-00408-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County. Sec. 5 Twp. 9 Rge. (E) 18 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE $\frac{1}{4}$ SE $\frac{1}{4}$ SW $\frac{1}{4}$
Lease Owner Lewis Drilling Company, et al
Lease Name Hilgers Well No. 1
Office Address 607 Union National Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 6-19-51 19
Application for plugging filed 6-19-51 19
Application for plugging approved 6-19-51 19
Plugging commenced 6-19-51 19
Plugging completed 6-19-51 19
Reason for abandonment of well or producing formation Dry

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3550 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	152	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

15 SX cement @ 150'
Hole filled with mud to 40'
10 SX cement on top

RECEIVED
STATE CORPORATION COMMISSION
8/11/51
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Lewis Drilling Company
Address 607 Union National Bank Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
L. L. Bailey (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. L. Bailey
607 Union National Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 22 day of June, 19 51

Arthur P. Derrington
Notary Public.

My commission expires August 20, 1952

PLUGGING
FILE SEC 5 T 9 R 20
BOOK PAGE 90 LINE 19

28-5091-s

8-50-10M

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY Lewis Drilling Company, et al

SEC. 5 T. 9 R. 18W

FARM Hilgers NO. 1

LOC. SE $\frac{1}{4}$ SE $\frac{1}{4}$ SW $\frac{1}{4}$

TOTAL DEPTH 3550'

COMM. 6-11-51


COMP. 6-19-51

COUNTY Rooks
KANSAS

SHOT OR TREATED

CONTRACTOR Lewis Drilling Company

ISSUED



CASING

20 10
15 8-5/8" 152'
12 6
13 5

ELEVATION 2048 DF

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

- 0 - 150 Surface sand and clay
- 150 - 275 Blue Shale
- 275 - 1170 Sand, Shale, and Shells
- 1170 - 1375 Red Bed-Shales
- 1375 - 1460 Shale and Shells
- 1460 - 1495 Anhydrite
- 1495 - 2015 Shale, Lime, and Shells
- 2015 - 2210 Brown Lime
- 2210 - 2335 Shale, Lime, and Shells
- 2335 - 2755 Brown Lime
- 2755 - 2830 Shale, Lime Stk.
- 2830 - 3090 Lime Shale
- 3090 - 3190 Lime
- 3190 - 3240 Lime and Shale
- 3240 - 3395 Lime
- 3395 - 3488 Lime Shale
- 3488 - 3497 Arbuckle
- 3497 - 3530 Lime
- 3530 - 3550 Cherty Lime
- 3550 - TD

GEOLOGICAL TOPS

Topeka	3000
Hessner Shale	3204
Dodge	3220
Lansing-Kansas City	3247
Arbuckle	3488

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.

RECEIVED
STATE CORPORATIONS COMMISSION
8/11/51
AUG 11 1951
CONSERVATION DIVISION
Wichita, Kansas

L. L. Bailey, Lewis Drilling Company, of lawful age, being first duly sworn under oath, states that the Lewis Drilling Company was the Contractor engaged for the drilling of the Hilgers No. 1, located in the Southeast Quarter of the Southeast Quarter of the Southwest Quarter (SE $\frac{1}{4}$ SE $\frac{1}{4}$ SW $\frac{1}{4}$) of Section 5, Township 9, Range 18 West, Rooks County, Kansas, and that the foregoing log is a true and correct copy of the log of the completed well.

LEWIS DRILLING COMPANY

By L. L. Bailey
L. L. Bailey

Subscribed and sworn to before me, a Notary Public, in and for the county and state above mentioned, this 22nd day of June, 1951.

Arthur R. Derrington
Notary Public

My commission expires August 20, 1952.

PLUGGING
5 9 18W
70 19