


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Rooks County, Sec. 10 Twp. 9 Rge. 18 XXW  
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines  
NE SW NE



Locate well correctly on above  
Section Plat

Lease Owner Graves Drilling Co., Inc.  
Lease Name Hageman Well No. 1  
Office Address 910 Union Center, Wichita, KS 67202  
Character of Well (Completed as Oil, Gas or Dry Hole)  
Dry Hole

Date Well completed 10-26 19 79  
Application for plugging filed 10-26 19 79  
Application for plugging approved 10-26 19 79  
Plugging commenced 10-26 1979  
Plugging completed 10-26 19 79  
Reason for abandonment of well or producing formation  
Dry Hole

If a producing well is abandoned, date of last production  
19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt  
Producing formation Depth to top Bottom Total Depth of Well 13,510'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe				8 5/8"	208'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from feet to  
feet for each plug set.

1st plug was set @ 745' w/70 sacks cement

2nd plug was set @ 200' w/20 sacks cement

3rd plug was set @ 40' w/5 sacks cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Dreiling Oil, Inc.

STATE OF KANSAS COUNTY OF ELLIS, ss.

I, Joseph A. Hess, Sec. Treas. of Drlg. Contrc. (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature)

JOSEPH A. HESS, HAYS, KS 67601

(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of October, 19 79

Cecilia Basgall  
Cecilia Basgall Notary Public.

My commission expires November 16, 1980.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 6 1979  
11-1-79  
CONSERVATION DIVISION  
Wichita, Kansas

CECILIA BASGALL  
NOTARY PUBLIC  
Ellis County, Kansas

# DREILING OIL, INC.

Victoria, Kansas 67671

## Graves Drilling Co. Inc. WELL LOG

910 Union Center  
Wichita, KS 67202

Company	Wichita, KS 67202	Sec. 10	Twp. 9	Rng. 18
Farm	Hageman No. 1	Location	NE SW NE	
Total Depth	3,510'	County	Rooks	
Comm.	10-18-79	Comp.	10-26-79	Elevation: 2014 K. B.
Contractor	Dreiling Oil, Inc. Rt. #1 Victoria, KS 67671			2011 D. F. 2009 G. R.

Casing Record  
208' - 8 5/8"

Cement Record  
cemented w/145 sacks

Production:  
D & A

### Figures Indicate Bottom of Formations

0'	35'	Post Rock
35'	890'	Shale & Sand
890'	1000'	Sand
1000'	1383'	Shale & Sand
1383'	1425'	Anhydrite
1425'	2000'	Shale
2000'	2196'	Shale & Lime
2196'	3115'	Lime & Shale
3115'	3510'	Lime
3510'	T.D.	

STATE OF KANSAS)  
)ss  
COUNTY OF ELLIS)

I, Joseph A. Hess, Secretary Treasurer of Dreiling Oil, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from the Hageman #1.

  
JOSEPH A. HESS

Subscribed and sworn to before me this 31st day of October, 1979.

  
Cecilia Basgall Notary Public

My appointment expires: November 17, 1980.

CECILIA BASGALL  
NOTARY PUBLIC  
Ellis County, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

NOV 01 1979

CONSERVATION DIVISION  
Wichita, Kansas