

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

LARSON OPERATING COMPANY
Lease Operator: A DIVISION OF LARSON ENGINEERING, INC.
Address: 562 WEST STATE ROAD 4 OLMITZ, KS 67564-8561
Phone: (620) 653-7368 Operator License #: 3842
Type of Well: oil Docket #: _____
(Oil, Gas, D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 12-13-06 (Date)
by: Bill Johnson (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Simpson Depth to Top: 2944' Bottom: _____ T.D. _____
Viola Depth to Top: 2932' Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. 3085'

API Number: 15-015-22169-00-00
Lease Name: Corbin
Well Number: 4
Spot Location (QQQQ): SW - NW - NE -
990 Feet from North / South Section Line
2310 Feet from East / West Section Line
Sec. 6 Twp. 27 S. R. 4 East West
County: Butler
Date Well Completed: 11-15-82
Plugging Commenced: 12-20-06
Plugging Completed: 1-08-07 *Rev 12-20-06 CP2/3*

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Viola	oil	surface	213'	8-5/8"	213'	none
		surface	3084'	5-1/2"	3084'	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same, depth placed from (bottom), to (top) for each plug set.

Spotted 60 sx of 60-40 poz w/2% CC thru tbg @ 1148'. WOC 1 hr & tagged cmt @ 1089'. Perf 5-1/2" @ 265'. TIH w /tbg to 265'.
Pumped 58 sx 60-40 poz thru tbg & circ thru perms @ 265' - circ cmt from 265' to surface in 5-1/2"x 8-5/8" annulus. Pumped 57 sx 60-40 poz thru tbg & circ from 265' to surface in 5-1/2" casing. TOH w/ tbg. 1-8-07 RIH w/ 190' 1-1/4" poly pipe.
Pumped 55 sx of class A thru poly pipe from 190' to surface in 5-1/5 csg x 8-5/8 annulus. Cmt 5' down from surface 1-9-07.


Name of Plugging Contractor: United Cementing License #: 30437
Address: 2510 w 6th St, El Dorado Kansas, 67042
Name of Party Responsible for Plugging Fees: LARSON OPERATING COMPANY, A DIVISION OF LARSON ENGINEERING, INC.
State of KANSAS County, BARTON, ss.

CAROL LARSON (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Carol Larson SECRETARY/TREASURER
(Address) 562 WEST STATE ROAD 4 OLMITZ, KS 67564-8561

RECEIVED
JAN 19 2007
KCC WICHITA

SUBSCRIBED and SWORN TO before me this 18TH day of JANUARY, 2007
Stacey Tedrow My Commission Expires: _____
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Handwritten initials