

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: T-N-T Engineering, Inc.
Address: 3711 Maplewood, Ste 201, Wichita Falls, TX 76308
Phone: (940) 691-9157 ext. 113 Operator License #: 33699

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: _____ (Date)

by: Herb Deines (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

LKC "A" Depth to Top: 3458 Bottom: 3466 T.D. _____
Arbuckle Depth to Top: 3730 Bottom: 3774 T.D. 3915
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-009-24354-00-00

Lease Name: Leslie Deckert

Well Number: 1-7

Spot Location (QQQQ): SW - SE - SE -
330 Feet from North / South Section Line

990 Feet from East / West Section Line

Sec. 7 Twp. 20 S. R. 15 East West

County: Barton

Date Well Completed: _____

Plugging Commenced: 12-15-06

Plugging Completed: 12-27-06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	1064	
				5 1/2	3912	1930

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sand at 3400', bailed 5 sacks cement with bailer, pulled stretch, had 18", ripped casing at 2210', worked pipe, ripped casing at 2040', worked pipe, ripped casing at 1930', came free, pulled casing up to 1750', pumped 120 sacks, 3 hulls at 1750', pulled casing up to 1050', pumped 40 sacks, 1 hull, pulled casing up to 250', circulated with 40 sacks, pulled casing out, emptied pit.

Name of Plugging Contractor: Quality Well Service License #: 31925

Address: 401 W Main, Lyons, KS 67554

Name of Party Responsible for Plugging Fees: T-N-T Engineering, Inc.

State of Texas County, Wichita, ss.

Hal Gill (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Hal Gill

(Address) 3711 Maplewood, Ste. 201, Wichita Falls, TX 76308

SUBSCRIBED and SWORN TO before me this 16th day of January 20 07

Susan A. Van Huss My Commission Expires: May 26, 2010
Notary Public

PPT