

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Pintail Petroleum, Ltd.

Address: 225 N. Market, #300, Wichita, KS 67202

Phone: (316) 263-2243 Operator License #: 5086

Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 12/8/2006 (Date)

by: Steve Durrant (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Kinderhook Sand Depth to Top: 4542 Bottom: 4546 T.D. 4600

API Number: 15-047-20391-00-00

Lease Name: Fisher 'S'

Well Number: 1

Spot Location (QQQQ): C - SE - SE -

660 Feet from North / South Section Line

660 Feet from East / West Section Line

Sec. 21 Twp. 26 S. R. 17 East West

County: Edwards

Date Well Completed: 6/20/2006 5/30/78

Plugging Commenced: 12-8-06 PER

Plugging Completed: 12-13-06 RBDMS
PKT

KCC 1/24/07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	261	
				4 1/2	4597	2200

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sand at 4490', bailed 4 sacks, set floor, pulled slips, ripped 2460', worked pipe, not loose, ripped 2200', came loose, pulled to 1200', pumped 15 gel & 50 sacks cement, pulled up to 300', loaded hole with water, pumped 100 sacks, well went on vacuum, shut down pump truck, pulled casing out, checked hole, plug at 320', ran casing back down to 300', circulated with 150 sacks to surface, pulled casing out, emptied pit, cleaned up location.

Name of Plugging Contractor: Quality Well Service License #: 31925

Address: 401 W Main, Lyons, KS 67554

Name of Party Responsible for Plugging Fees: Pintail Petroleum, Ltd.


State of Kansas County, Sedgwick, ss.

Beth A. Isern (Employee of Operator) or (Operator) KCC WICHITA being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Beth A. Isern

(Address) 225 N. Market, Ste. 300, Wichita, KS 67202



and SWORN TO before me this 18 day of January, 2007

My Commission Expires: 12/14/2009
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT