

15-163-03360-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER none

LEASE NAME Stahl

WELL NUMBER #3

3300 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 17 TWP. 9 RGE. 18 ~~E~~ (W)

COUNTY Rooks

Date Well Completed 11-18-49

Plugging Commenced 10:00am 4-9-91

Plugging Completed 4-9-91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR The Gene Brown Company

ADDRESS Drawer 220 Plainville, Ks. 67663

PHONE# (913) 434-4811 OPERATORS LICENSE NO. 5635

Character of Well oil

(Oil, ~~Gas, P&A, SWD, Inert, Water Supply Well~~)

The plugging proposal was approved on March 26, 1991 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? no If not, is well log attached? none

Producing Formation Arbuckle Depth to Top 3530 Bottom 3541 T.D. 3541

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|--------------------|-------------|------|----|-------|--------|------------|
| surface production | fresh water | | | 8 5/8 | 240 | none |
| | oil | | | 5 1/2 | 3530 | none |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Perforate 5 1/2 casing at 1500 & 900 - Pumped 25 sks cement with 1/4# flocele and then pumped 225 sks cement with 1/2 flocele with 400# Hulls at 800# pressure and shut in at 300#. Then pumped 50 sks cement with 1/2# flocele with 100# Hulls down 10 inc. surface pipe at 900# pressure and shut in at 100# pressure.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. 5287

Address Hays, Kansas **RECEIVED**
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: The Gene Brown Company

STATE OF Kansas COUNTY OF Rooks, ss.

Thomas M. Brown (Employee of Operator) ~~of~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Thomas M Brown

(Address) Drawer 220 Plainville

SUBSCRIBED AND SWORN TO before me this 14th day of May, 1991

Kathy A. Wise Notary Public

