

API NUMBER 15-163-22,120-00-00

LEASE NAME Hilgers B

WELL NUMBER 6

3630 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 17 TWP. 9 S RGE. 18 W or (W)

COUNTY Rooks

Date Well Completed 9-30-83

Plugging Commenced 12-13-96

Plugging Completed 12-13-96

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR AFG Energy Inc.

ADDRESS P.O. Box 458 Hays, Ks. 67601-0458

PHONE#(913) 625-6374 OPERATORS LICENSE NO. 03456

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-13-96 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Arbuckle-L-KC Depth to Top 3249' Bottom 3535' T.D. 3535'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
L-KC	Oil & Water	3249'	3486'	8 5/8"	267	None
Arbuckle	Oil & Water	3530'	3535'	5 1/2"	3530'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Tied to 8 5/8" & pressured to 700#. Ran 2 7/8" Tubing to 3516' open ended. Mixed 140 sxs. 60/40 Poz., 10% gel & 300# Hulls. Pulled up to 1507'. Mixed 130 sxs. of same & 200# Hulls. Cement circulated. Pulled tubing tied to 5 1/2". Mixed 25 sxs. of same. Pressured to 700#. SIP = 500#.

Name of Plugging Contractor Allied Cementing License No. _____

Address Russell, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: AFG Energy Inc.


STATE OF Kansas COUNTY OF Ellis, ss.

Terry W. Piesker (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Terry W. Piesker

(Address) P.O. Box 458 Hays, Ks. 67601-0458



AND SWORN TO before me this 16th day of December, 19 96

Linda K. Pfannenstiel
 Notary Public

My Commission Expires: 2/5/2000

USE ONLY ONE SIDE OF EACH FORM