

API NUMBER 15-163-22,077-00-00

LEASE NAME Hilgers "B"

WELL NUMBER #5

3630 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 17 TWP. 9 SRGE. 18 (E) or (W)

COUNTY Rooks Co.

Date Well Completed 7/13/83

Plugging Commenced 11/22/96

Plugging Completed 11/22/96

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR AFG Energy Inc.

ADDRESS P.O. Box 458 Hays, Kansas 67601-0458

PHONE# (913) 625-6374 OPERATORS LICENSE NO. 03456

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-20-96 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Arb - L-KC. Depth to Top 3187' Bottom 3520' T.O. 3520'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	Oil & Water	3517'	3520'	5/8"	288	None
	Oil & Water	3187'	3259'	3 1/2"	3517	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Ran 2 7/8" tubing to 3494". Hooked to 8 5/8" & Pressured to 500#. Hooked to 2 7/8" & mixed 350# Hulls & 150 SX. 60/40 Poz, 10% gel. Pulled tubing to 1490' and mixed 90 sxs. of same. Circulated to surface. Pulled tubing. Hooked to 5 1/2" and mixed 10 sxs. of same. Pressured to 500#.

Name of Plugging Contractor Allied License No. _____

Address Russell, Ks.

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: AFG Energy Inc.


STATE OF Kansas COUNTY OF Ellis, ss.

Terry W. Piesker (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Terry W. Piesker

(Address) P.O. Box 458 Hays, Ks. 67601-0458



AND SWORN TO before me this 4th day of Dec., 19 96

Linda K. Pfannenstiel
 Notary Public

My Commission Expires: 2/5/2000

USE ONLY ONE SIDE OF EACH FORM