


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County. Sec. 17 Twp. 9S Rge. 18W (E) (W)
Location as "NE/CNW/SW" or footage from lines NW/NW/NE
Lease Owner Frank J. Black SW
Lease Name Elizabeth Well No. 2
Office Address Box 150, McPherson, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 12-22 1949
Application for plugging filed 11-18 1957
Application for plugging approved 11-19 1957
Plugging commenced 12-6 1957
Plugging completed 12-13 1957
Reason for abandonment of well or producing formation Unprofitable



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3528 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1459'	None
				5-1/2"	3527'	2947'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Measured into T.D. 3528'.
Plugging started 12-6-57. Finished 12-13-57.
Plugged off bottom with sand to 3520' and dumped 4 sacks cement.
Shot 5 1/2" casing at 2,947'. Pumped 20 sacks cement. Pulled pipe to 200'.
Pumped 20 sacks more cement. Pulled rest of pipe and mudded to 35'. Set
rock bridge and mixed 10 sacks cement for cap on well. Well completed.

RECEIVED
STATE CORPORATION COMMISSION
12-21-57
DEC 21 1957
DIVISION

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor J.O. Forbes d/b/a Forbes Casing Pulling Co.
Address Box 221, Great Bend, Kansas

STATE OF Kansas COUNTY OF McPherson, ss.
Frank J. Black (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Frank J. Black

SUBSCRIBED AND SWORN TO before me this 20 day of Dec, 1957

My commission expires Jan 10 1961 Earl Nelson Notary Public.

PLUGGING
FILE SEC. 17 9 R 18W
BOOK PAGE 62 LINE 10

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 E. Murdock, Wichita, Kansas


COPY

Company - GULF OIL CORPORATION
Farm - Elizabeth No. 2

SEC. 17 T. 9 R. 18W
SW NW NE

Total Depth. 3528
Comm. 12-3-49 Comp. 12-22-49
Shot or Treated.
Contractor.
Issued. 7-8-50

County. Rocks
KANSAS



Elevation. _____

Production. 153 bbls.

CASING:

8 5/8" 1459' cem. w/600 sx.
5 1/2" 3527' cem. w/100 sx.

Figures indicate Bottom of Formations.

shale	270
shale & shells	590
sand & shale	660
shale & shells	975
sand	1150
shale & shells	1200
sand & shale	1449
anhyd.	1480
shale & shells	1675
shale & lime	2045
shale & shells	2230
lime	2242
lime & shale	2520
shale & lime	2652
lime	3105
lime & shale	3175
lime	3274
lime & shale	3290
lime	3475
lime & shale	3514
shale & lime	3520
lime	3528
Total Depth	

Tops:	
Reebner	3234
Toronto	3255
Lansing	3272
Arbuckle	3526

Acidized w/500 gals. 12-21-49

RECEIVED
STAFF CORPORATION COMMISSION
DEC 21 1957
DIVISION

PLUGGING
FILE SEC 17 T. 9 R. 18W
BOOK PAGE 62 LINE 10