

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Rooks County. Sec. 17 Twp. 9S Rge. 18 (E) X (W)

Location as "NE/CNW/SW" or footage from lines NW/NW/NE

Lease Owner Frank J. Black

Lease Name Elizabeth Well No. 1

Office Address Box 150, McPherson, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 12-23 1948

Application for plugging filed 11-18 1957

Application for plugging approved 11-19 1957


Plugging commenced 12-4 1957

Plugging completed 12-9 1957

Reason for abandonment of well or producing formation Unprofitable

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3524 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		2924'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Measured into T.D. 3524'.  
Plugging started 12-4-57. Finished 12-9-57.  
Plugged off bottom with sand to 2510' and dumped 4 sacks cement.  
Shot 5 1/2" casing at 2,924'. Pumped mud and balanced same.  
Pulled pipe to 600'. Pumped 20 sacks cement. Pulled pipe to 200'.  
Pumped 20 sacks cement. Layed down rest of pipe. Bailed down to 35'.  
Set rock bridge and mixed 10 sacks cement for cap on well. Well completed.

RECEIVED  
STATE CORPORATION COMMISSION

DEC 20 1957  
12-20-57  
DIVISION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J.O. Forbes d/b/a Forbes Casing Pulling Co.

Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF McPherson, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

(Address) [Address]

SUBSCRIBED AND SWORN TO before me this 19 day of Dec 19 57

[Signature] Notary Public.

My commission expires Jan 10, 1961

PLUGGING  
FILE SEC 17 9 R 18W  
BOOK PAGE 62 LINE 9

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY  
508 E. Murdock, Wichita, Kansas

15-163-03356-00-00


COPY

Company - GULF OIL CORPORATION  
Farm - Elizabeth No. 1

SEC. 17 T. 9 E 18W  
NW NW NE

Total Depth. 3524  
Comm. 11-30-48 Comp. 12-23-48  
Shot or Treated.  
Contractor.  
Issued. 7-8-50

County. Rocks  
KANSAS



CASING:  
8 5/8" 1450' cem. w/600 sx.  
5 1/2" 3520' cem. w/100 sx.

Elevation. \_\_\_\_\_  
D. D.  
Production. 1032 bbls. /  
20 bbls. wtr.

Figures Indicate Bottom of Formations.

surface dirt	40
sand & shale	190
shale & shells	775
sand & shale	1100
shells & shale	1215
red bed, shale & shells	1285
red bed & shale	1300
red bed	1445
anhyd.	1480
red bed, shale & shells	1590
shale & shells	1860
shale & lime	3135
lime RTD ?	3522
lime	3524
Total Depth	

Tops:	
Heebner	3226
Toronto	3245
Base Oread	3259
Lansing	3266
Marmaton	3490
Simpson	3510
Arbuckle	3519

Acidized w/100 gals. 12-20-48  
Acidized w/300 gals. 12-22-48

**RECEIVED**  
STATE CORPORATION COMMISSION  
12-20-57  
DEC 20 1957  
COMMISSION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 17 T 9 R 18W  
BOOK PAGE 62 LINE 9