


STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD



Rooks County. Sec. 17 Twp. 9 Rge. 18 (E) (W)  
Location as "NE/CNW/SW" or footage from lines NW NE SW  
Lease Owner Petroleum, Inc.  
Lease Name Ruzicka Well No. 2  
Office Address 305 East Third, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed August 1, 19 52  
Application for plugging filed August 1, 19 52  
Application for plugging approved August 1, 19 52  
Plugging commenced August 1, 19 52  
Plugging completed August 1, 19 52  
Reason for abandonment of well or producing formation Dry Hole

Locate well correctly on above Section Plat  
Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty  
Producing formation Depth to top Bottom Total Depth of Well 3591 Feet  
Show depth and thickness of all water, oil and gas formations.

| OIL, GAS OR WATER RECORDS |         |      |    |        | CASING RECORD |            |
|---------------------------|---------|------|----|--------|---------------|------------|
| FORMATION                 | CONTENT | FROM | TO | SIZE   | PUT IN        | PULLED OUT |
|                           |         |      |    | 8 5/8" | 220'          | None       |
|                           |         |      |    |        |               |            |
|                           |         |      |    |        |               |            |
|                           |         |      |    |        |               |            |
|                           |         |      |    |        |               |            |
|                           |         |      |    |        |               |            |
|                           |         |      |    |        |               |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up to 210' and set wooden plug at 210'.  
Placed 1/2 sack hulls on top of plug set at 210'.  
Cemented and displaced 15 sacks cement through  
drill pipe onto plug at 210'. Mudded up to 35'  
and set second wooden plug. Placed 1/2 sack hulls  
onto wooden plug set at 35'. Filled hole to  
bottom of well cellar with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Garvey Drilling Company  
Address R. R. #2

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Charlotte Weidman (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charlotte Weidman  
305 East Third, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of August, 19 52  
My commission expires October 27, 1952  
Notary Public.

DRILLER'S LOG RUZICKA #2

Petroleum, Inc., Operator

Section 17, Twp. 9S, Rge. 18W

Garvey Drilling Company, Contractor

Location: NW NE SW

Drilling Commenced: July 23, 1952  
Drilling Completed: August 1, 1952

County: Rooks County, Kansas

Casing Records: 8 5/8" @ 220' w/145 sax

R. T. D.: 3591'

Production: D &amp; A

Figures below indicate bottom of formation:

|      |                |
|------|----------------|
| 70   | Surface soil   |
| 220  | Clay and Sand  |
| 1050 | Shale & Shells |
| 1230 | Sand           |
| 1514 | Shale & Shells |
| 1550 | Anhydrite      |
| 2150 | Shale & Shells |
| 3295 | Lime & Shale   |
| 3546 | Lime           |
| 3575 | Lime & Shale   |
| 3591 | Lime & Shale   |

## Tops:

|          |              |
|----------|--------------|
| Heebner: | 3280 (-1154) |
| Lansing: | 3321 (-1195) |
| Simpson: | 3574 (-1448) |

3591' R.T.D.

I hereby certify that this is a true and correct log of the above mentioned well.

PETROLEUM, INC.

By Charlotte Menden

STATE OF KANSAS )  
COUNTY OF SEDGWICK ) SS:

Subscribed to and sworn to before me, this 18th day of August, 1952,

Marjorie Bradshaw  
Notary Public

My commission expires: October 27, 1952.

**PLUGGING**

FILE SEC 17 T 9 R 18 W  
BOOK PAGE 35 LINE 26