


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Rooks \_\_\_\_\_ County. Sec. 17 Twp. 9 Rge. (E) 18(W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines 990'N 990'E of S/4 Corner  
Lease Owner Cities Service Oil Co.  
Lease Name Baumgartner "E" Well No. 2  
Office Address Bartlesville, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed 11-4-53 19  
Application for plugging filed 11-4-53 19  
Application for plugging approved 11-5-53 19  
Plugging commenced 11-5-53 19  
Plugging completed 11-5-53 19  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty  
Producing formation Arbuckle Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3631 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	dry			8-5/8	268'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Fill with heavy mud to 240', set bridge plug at 240'. Run 15 sacks cement through drill pipe. Fill with heavy mud to 40' of surface, one-half sack hulls, ten sacks cement to surface.

11-27-53

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lohmann-Johnson  
Address Evansville, Indiana

STATE OF KANSAS, COUNTY OF BARTON, ss.

James Porter (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James Porter

Box 553, Russell, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 17th day of November, 1953

W. E. Smith  
Notary Public.

My commission expires 3-17-1955

PLUGGING  
FILE SEC 17 T 9 R 18  
BOOK PAGE 142 LINE 24

# WELL RECORD

Company..... Cities Service Oil Co. Well No. 2 Farm Langgartner #2  
 Location..... 990' North and 990' East of S/4 Cor. Sec. 17 T. 9 R. 18W  
 Elevation..... 2141 (2139 Gr.) County \_\_\_\_\_ Rocks \_\_\_\_\_ State Kansas  
 Drlg. Comm. October 26, 1953 Contractor Lohmann-Johnson Drilling Co., Inc.  
 Drlg. Comp. November 4, 1953 Acid None  
 T. D. 3631' Initial Prod. Dry Hole - P. & A. 11-4-53.

CASINO RECORD:  
8-5/8" @ 268' w/ 175 cc cement

FORMATION RECORD:

shale & sand	0-268
sand & shale	560
sand, shale & shells	1060
sand	1230
shale & red bed	1500
anhydrite	1540
shale & shells	1940
shale & lime	2160
shale & shells	2356
broken lime	2470
shale & lime	2580
lime & shale	3232
lime	3330
lime & shale	3379
lime	3574
lime & shale	3605
lime	3631 T. D.

Topoka	3089'
Beckner	3300'
Rodge	3320'
Landing	3341'
Simpson	3396'
Arbuckle	3609'
Penetration	38'
Total Depth	3631'

Drill Stem Test 3604-10,  
 open 1 hr., recovered 6'  
 mud; B. N. P. 0/15 mins.

SLOPE TEST (ACID BOTTLE):

500'	0°
1000'	0°
1500'	0°
2000'	0°
2500'	0°
3000'	0°

7-7/8" rotary hole.

**PLUGGING**  
 FILE SEC-17 T-9 R-1840  
 BOOK PAGE 142 LINE 24