

State of Kansas



15-163-20254-00-00

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

10/13/69
 RECEIVED
 STATE CORPORATION COMMISSION
 OCT 13 1969
 CONSERVATION DIVISION
 Wichita, Kansas

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Haston of Dreiling Drlg. has this date requested permission to plug the following described well:

Mr. Haston guarantees payment of the plugging fee.

Operator's full Name: H. B. Mabee & Dreiling

Complete Address: Box 94718 Okla. City, Okla.

Lease Name: Lewis Well No. 1

Location: NW SW SE Sec. 32 Twp. 8 Rge. (E)(W) 17

County: Rooks Total Depth 3471' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Haston was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 720' and displace
70 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Scott Mueser
 Conservation Division Agent