

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
8/29/66
AUG 29 1966
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Crowe of Garvey Drlg. Co. has this date requested permission to plug the following described well:

Mr. Crowe guarantees payment of the plugging fee.

Operator's full Name: Petroleum Inc.

Complete Address: 300 west Douglas Wichita, Kansas

Lease Name: Meistreill "E" Well No. 1

Location: SW NE NE Sec. 5 Twp. 9 Rge. 18 (E)(W) X

County Rooks Total Depth 3478 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Crowe was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 540'
and displace 20 sc cement thru drillpipe. Heavy mud to 210' set
cementing plug and displace 20 sc cement thru drill pipe. Heavy
mud to 40' set cementing plug 1/3 sc hulls and 10 sc cement to
base of celler. Plug rat hole with 2 sc cement.

Very truly yours,

Bob Massey
Conservation Division Agent