

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
SEP 1 1966
9-1-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Crowe of Garvey Drilling Co. has this date requested permission to plug the following described well:

Mr. Crowe guarantees payment of the plugging fee.

Operator's full Name: Petroleum Inc.,

Complete Address: 300 West Douglas Wichita, Kansas

Lease Name: Shaw Estate Well No. 1

Location: C SE SE Sec. 10 Twp. 9 Rge. 18 (E)(W) X

County Rooks Total Depth 3235' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Crowe was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 540'
and displace 25 sc cement thru drill pipe. Heavy mud to 210 Ft.
set cementing plug and displace 20 sc cement thru drill pipe.
Heavy mud to 40' set cementing plug, 1/3 sc hulls and 8sc
cement to base of celler. Plug rat hole with 2 sc cement.

Very truly yours,

[Signature]
Conservation Division Agent