

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 173-01630-0003 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 3/26/1964

Well Operator: W. D. Short Oil Co., LLC KCC License #: 33608
(Owner / Company Name) (Operator's)

Address: P.O. Box 729 City: Oxford

State: Kansas Zip Code: 67119 Contact Phone: (620) 455 - 3576

Lease: O.S.A. Well #: 15 Sec. 15 Twp. 29 S. R. 1 East West

- SE - SW - NE Spot Location / QQQQ County: Sedgwick

2010 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

1650 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8-5/8" Set at: 308' Cemented with: 300sx Sacks

Production Casing Size: 5-1/2" Set at: 3725' Cemented with: 100sx Sacks

List (ALL) Perforations and Bridgeplug Sets: Perforations @ 3360-72, Bridge Plug @ 3503'

Elevation: 1189 (G.L. / K.B.) T.D.: 3725 PBTD: 3503 Anhydrite Depth: NA
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Per KCC Regs.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: John Longbine

Phone: (620) 218 - 1821

Address: P.O. Box 729 City / State: Oxford, Kansas 67119

Plugging Contractor: W. D. Short Oil Co., LLC KCC License #: 33608
(Company Name) (Contractor's)

Address: P.O. Box 729, Oxford, Ks. 67119 Phone: (620) 455 - 3576

Proposed Date and Hour of Plugging (if known?): 1-9-2007

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 1-11-2007 Authorized Operator / Agent: [Signature]
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202 **KCC WICHITA**

RECEIVED
JAN 16 2007

ROY #4

OSA # 15

Casing Record:

Company: Aylward Drilling Company
Contractor: ditto

Location: SE SW NE 15-29-1W
Sedgwick County
Kansas

8 5/8" - 308'
5 1/2" - 3725'

Commenced: March 16, 1964
Completed: March 26, 1964

Elev.: 1291 D.F. - 1294 RB



	<u>From</u>	<u>To</u>	<u>Remarks</u>
Sand	0	70	Set 8 5/8" surface pipe @ 308'
Lime & Shale	70	275	w/300 sacks.
Lime	275	597	
Lime & Shale	597	745	Geological Tops:
Lime	745	980	
Lime & Shale	980	2490	Stalnaker 2467
Sand & Shale	2490	2608	Kansas City 2788
Shale & Lime	2608	2795	Base Kansas City 3002
Lime	2795	3138	Mississippian 3370
Lime & Shale	3138	3385	Kinderhook 3662
Lime	3385	3668	Simpson Sand 3724
Sand	3668	3739 T.D.	
			DST 3374-90 Open 1 hr. Rec. 720' gas in pipe, 25' S10CM, 30' free oil, 15' HOCM, 25' OCMW, 30' water. IBHP 1310#/30" - FBHP 1191#/30" FP 26#-87#
			DST 3724-39 Open 5" prior to closing in. GTS when tool open, OTS/65" IBHP 1262#/30" - FBHP 1244#/31" FP 96#-945#
			Set 5 1/2" casing @ 3725' w/100 sacks.

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Charles W. Williams

Subscribed and sworn to before me this 30th day of March, 1964

Duane Jessup
Notary Public

My commission expires December 11, 1965

RECEIVED
JAN 16 2007
KCC WICHITA

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

W.D. Short Oil Co., LLC
102 S. River Road
PO Box 729
Oxford, KS 67119

January 23, 2007

Re: O S A UNIT #15
API 15-173-01630-00-03
SESWNE 15-29S-1W, 3270 FSL 1650 FEL
SEDGWICK COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely



Barry Metz
Deputy Director

District: #2
3450 N. Rock Road, Suite 601
Wichita, KS 67226
(316) 630-4000