

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-011-20393-00-00
Spot: NESWSESE Sec/Twnshp/Rge: 7-24S-22E
380 feet from S Section Line, 816 feet from E Section Line
Lease Name: ERMEL D Well #: 7
County: BOURBON Total Vertical Depth: 710 feet

Operator License No.: 33247

Op Name: PETROL OIL & GAS, INC.

Address: 3161 E WARM SPRINGS ROAD, SUITE 3
LAS VEGAS, NV 89120

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.375	705	0	
SURF	7.625	21	0	

\$ 35.00

Well Type: EOR

UIC Docket No: E19329.1

Date/Time to Plug: 12/28/2006 1:00 PM

Plug Co. License No.: 31440

Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC

Proposal Rcvd. from: DALE MALEY

Company: PETROL OIL & GAS, INC.

Phone: (620) 496-6076

Proposed
Plugging
Method:

THIS WELL CONSISTED OF 2 3/8" CASING TO 705' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP.
THE PLUGGING PROPOSAL WAS TO CIRCULATE THE 2 3/8" CASING FULL OF CEMENT.

Plugging Proposal Received By: CLAYTON TITEL

Witness Type: NONE

Date/Time Plugging Completed: 12/28/2006 3:20 PM

KCC Agent: CLAYTON TITEL

Actual Plugging Report:

1" PIPE WAS RAN INTO THE 2 3/8" CASING TO 700'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2 3/8" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 15 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Perfs:

Top	Bot	Thru	Comments
655	667	CSG	

RECEIVED
KCC DISTRICT #3

JAN 17 2007 CPT

CHANUTE, KS

INVOICED

DATE 1-25-07

INV. NO. 2007061252

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 23 2007

CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: TBG

District: 03

Signed

Clayton P. Titel

(TECHNICIAN)

PRT