

To: 6 041041
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

S-24 15-163-01532-00-00
8-20-48
API NUMBER 15-

TECHNICIAN'S PLUGGING REPORT

Operator License # 3613

Operator: Quinoco Pet Inc.
Name & Address 915 Patton Rd.
Great Bend, Ks. 67530

C SW NE NE, SEC. 6, T. 9 S, R 18 W&E
_____ feet from S section line
_____ feet from E section line

Lease Name E.A. Thompson Well # 5

County Rooks 113.62

Well Total Depth 3496 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Cementing License Number _____

Address Hays, Ks.

Company to plug at: Hour: 8:00 Day: 24 Month: May Year: 19 89

Plugging proposal received from George Hutton

(company name) Quinoco (phone) _____

were: 6" casing set at 3493' w/150 sks. Top perf at 3239';
Perf anhy at 1458' and base dakota at 825'. Ordered 400 sks 65/35 Poz 10% gel w/1/4# F.C.
plus 500# Hulls.

RECEIVED
STATE CORPORATION COMMISSION
6/6/89
JUN 6 1989
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:55PM Day: 24 Month: May Year: 19 89

ACTUAL PLUGGING REPORT Pumped in 6" caisnt 335 sks cement w/1/4# f.c. plus 500#

hulls mixed in cement. Max 300# S.I. 200# psi. Pumped in 10 3/4" casing 75 sks cement
w/1/4# f.c. Max 200# S.I. 100# psi.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED
Please observe this plugging.

DATE 6-8-89

INV. NO. 25018

S-24

J. S.

Signed Dennis L. Hamel
(TECHNICIAN)

Dennis L. Hamel