

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-207-01973-00-00
Spot: NENENE Sec/Twnshp/Rge: 4-24S-14E
330 feet from N Section Line, 330 feet from E Section Line
Lease Name: WOLFE Well #: 1
County: WOODSON Total Vertical Depth: 1688 feet

Operator License No.: 32044

Op Name: CROSS OIL, L.L.C.

Address: 101 S. 5TH ST. PO BOX 94
HAMILTON, KS 66853

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1688	700	

\$ 54.86

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 11/08/2006 8:00 AM

Plug Co. License No.: 31440

Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC

Proposal Rcvd. from: DENNIS SMITH & BRIAN M Company: CROSS OIL, LLC

Phone: (620) 437-6219

Proposed Plugging Method: TUBING AND PACKER HUNG IN HOLE, RUN 1" TO 1625' AND PUMP 20 SCKS CEMENT. THEN SHOOT TUBING OFF ABOVE PACKER AND PULL OUT, TAKE OUT APPROX 700' 4 1/2" CASING, RUN TUBING IN AND PUMP IN ENOUGH CEMENT FOR 50' BRIDGE OR MORE, PULL TUBING TO SURFACE SPECIFICATIONS AND PUMP CEMENT TO SURFACE.

Plugging Proposal Received By: CLAYTON TITEL

WitnessType: PARTIAL

Date/Time Plugging Completed: 11/17/2006 5:00 PM

KCC Agent: CLAYTON TITEL

Actual Plugging Report:

1" PIPE WAS RAN INTO THE WELL TO 1650'. 25 SACKS OF CEMENT WERE PUMPED INTO THROUGH THE 1" PIPE TO 1650. THE 1" PIPE WAS REMOVED. THE 2" TUBING WAS SHOT OFF AT 1220' AND REMOVED. THE 4 1/2" CASING WAS SHOT OFF AT 700' AND 700' OF 4 1/2" CASING WAS REMOVED FROM THE WELL. 2" TUBING WAS RAN INTO THE WELL TO 700'. 10 SACKS OF CEMENT WERE PUMPED THROUGH THE 2" TUBING TO 700'. THE TUBING WAS PULLED TO 200'. CEMENT WAS PUMPED INTO THE 2" TUBING UNTIL CEMENT CIRCULATED FROM THE WELL AT SURFACE. THE 2" TUBING WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

Perfs:

Top	Bot	Thru	Comments
1672	1677		

RECEIVED
KCC DISTRICT #3

JAN 24 2007 CPT

CHANUTE, KS

INVOICED

DATE 1-30-07

INV. NO. 2007061274

Remarks:

Plugged through:

District: 03

Signed

Clayton P. Titel

(TECHNICIAN)

RECEIVED

Form CP-2/3

JAN 29 2007

KCC WICHITA

[Handwritten signature]