

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-053-00786-00-01  
Spot: SWSESE Sec/Twnshp/Rge: 16-17S-8W  
349 feet from S Section Line, 1084 feet from E Section Line  
Lease Name: RATHBUN OWWO A <sup>KCC AB</sup> Well #: 1  
County: ELLSWORTH Total Vertical Depth: 3247 feet

Operator License No.: 5088  
Op Name: DARRAH, JOHN JAY, JR.  
Address: 225 NORTH MARKET, STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
L1	4	1265		
PROD	5.5	3241		
SURF	8.625	216		

\$ 105.53

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/08/2006 10:00 AM  
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.  
Proposal Rcvd. from: GERALD DONOVAN Company: CLASSIC WELL SERVICE, INC. Phone: (620) 786-0935

Proposed Plugging Method: Pump 7 sacks at 3150' and tag. Perforate at 1100' and spot 35 sacks of cement. Perforate at 775' and spot 35 sacks of cement. Perforate at 270' and circulate cement to the surface.

Plugging Proposal Received By: DOUG LOUIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/20/2006 12:30 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

11/8/2006 -- Ran 2-3/8" tubing to 3215' and spotted 50 sacks of cement with 50 lbs of cotton hulls. Pulled tubing to 1079'. Ran perforation tool to 1100' and shot casing.

11/9/2006 -- Ran 2-3/8" tubing to 3143' and tagged bottom plug. Pulled tubing to 1115' and spotted 35 sacks of cement. Pulled tubing to 774'. Ran perforation tool to 775' and shot casing. Spotted 35 sacks of cement at 775'. Pulled tubing to 274'. Ran perforation tool to 280' and shot casing. Circulated water in all annuli. Pumped 350 sacks of cement, but did not circulate cement to surface.

11/13/2006 -- Checked top plug. Ran string line to 285' inside of 4-1/2" casing. Notified operator.

11/16/2006 -- Gressel Oil Field Service ran wireline to 286' and tagged cement. Ran perforating tool to 270' and reperfomed casing.

11/20/2006 -- Greg Eves witnessed the 4" collar welded onto the 4" liner and circulated 200 sacks of cement to the surface in all annuli.

670 sacks of 60/40 posmix with 4% gel  
Copeland #031329 & #031182

Perfs:

RECEIVED  
KCC DISTRICT #2  
NOV 30 2006  
WICHITA, KS

INVOICED  
DATE 1-30-07  
INV. NO. 2007061275

Remarks: PLUGGED THROUGH CASING AND TUBING.

Plugged through: CSG

District: 02

Signed Michael Wilson  
(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION CP-2/3  
DEC 29 2006  
CONSERVATION DIVISION  
WICHITA, KS