

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-20697-00-00
Spot: NENE Sec/Twnshp/Rge: 17-17S-25W
660 feet from N Section Line, 660 feet from E Section Line
Lease Name: STUTZ Well #: 1
County: NESS Total Vertical Depth: 4475 feet

Operator License No.: 33605 •
Op Name: JOE GERSTNER OIL, LLC
Address: 302 E. SYCAMORE
NESS CITY, KS 67560

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1413		WITH 5 SX CMT
PROD	5.5	4464	0	WITH 100 SX CMT
SURF	8.625	247		WITH 175 SX CMT

\$ 145.44

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/18/2006 2:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: PAT GERSTNER Company: JOE GERSTNER OIL LLC Phone: (785) 798-2893

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING REPORT

Plugging Proposal Received By: _____ WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/16/2007 5:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:
SANDED TO 4400' & 5 SX CMT. SET BRIDGE PLUG @ 1413' WITH 5 SX CMT. PERFORATE AT 1150'. RUN TUBING TO 1140' & PUMP 120 SX CMT. WENT ON VACUUM. PULLED TUBING. TIED ONTO BACKSIDE & PUMPED 50 SX CMT. PRESSURED TO 500# & HELD. TIED ONTO CASING AND PUMPED 130 SX CMT & 400# HULLS. STILL ON VACUUM. TRIED TO TOP OFF WITH 70 SX CMT. 1/16/07: TOPPED OFF WELL WITH 35 SX CMT. HOLE STAYED FULL.

Perfs:

INVOICED
DATE 1-29-07
INV. NO. 2007061265

RECEIVED
JAN 25 2007
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND CEMENTING.

Plugged through: TBG

District: 01

RECEIVED
JAN 19 2007
KCC Dodge City

Signed Michael Maier
(TECHNICIAN)

Form CE-22
[Signature]