

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-23256-00-00  
Spot: SWNW Sec/Twnshp/Rge: 36-20S-24W  
3300 feet from S Section Line, 4620 feet from E Section Line  
Lease Name: MCCREIGHT Well #: 2  
County: NESS Total Vertical Depth: 4412 feet

Operator License No.: 31627  
Op Name: WHITETAIL CRUDE, INC  
Address: N HWY 283 PO BOX 544  
NESS CITY, KS 67560

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4360	1017	WITH 100 SX CMT
SURF	8.625	745		3105X KCC Pkt 1-29-07

Well Type: EOR UIC Docket No: E25615.1 Date/Time to Plug: 01/16/2007 11:15 AM  
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC \$ 143.39  
Proposal Rcvd. from: ROGER Company: WHITETAIL CRUDE, INC Phone: (785) 798-3641

Proposed Plugging Method: SAND TO 4340' & 5 SX CMT. PLUG AT 760' WITH 80 SX CMT. PLUG AT 350' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/16/2007 1:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SANDED TO 4340' & 5 SX CMT. 1ST PLUG AT 760;' WITH 80 SX CMT. 2ND PLUG AT 350' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4360	4412	OH	


**INVOICED**  
DATE 1-29-07  
INV. NO. 2007061268

**RECEIVED**  
**JAN 25 2007**  
**KCC WICHITA**

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01



Signed

*Michael Maier*  
(TECHNICIAN)

Form 01-23