

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Bowman Oil Company
Address: 805 Codell Road Codell, Kansas 67663
Phone: (785) 434-2286 MF 7-12AM Operator License #: 6931
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 7-28-05 (Date)
by: Dennis Hamel (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Arbuckle Depth to Top: 3730' Bottom: 3735' T.D. 3747'
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-065-20,788-00-00
Lease Name: Barber
Well Number: #3
Spot Location (QQQQ): NW - SE - SW - SE - SE
495 Feet from North / South Section Line
1,155 Feet from East / West Section Line
Sec. 23 Twp. 10 S. R. 21 East West
County: Graham County, Kansas
Date Well Completed: 10-17-1975
Plugging Commenced: 7-28-05 9:00 AM
Plugging Completed: 7-28-05

KCC
PCT
1-24-07
per
RBDms

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	oil & water	3730'	3735'	8 5/8"	260'	None
				5 1/2"	3735'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perfed casing at 1650' and 950'. RIH with tubing to 1900' - spotted 110 sxs cement with 100# hulls mixed in cement. Pulled tubing to 700' - spotted 50 sxs cement with 100# hulls mixed in cement - cement circulated at surface. POOH with tubing and squeezed casing with 50 sxs cement. Max. P.S.I. 800#. S.I.P. 300#. 8 5/8" surface pipe - squeezed 5 sxs cement. Max. P.S.I. 500 #. S.I.P. 250#.

Name of Plugging Contractor: Allied Cementing Company, Inc. License #: 99996
Address: P.O. Box 31, 24 S. Lincoln, Russell, Kansas 67665
Name of Party Responsible for Plugging Fees: Bowman Oil Company
State of Kansas County, Rooks, ss.

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 22 2007
CONSERVATION DIVISION
WICHITA, KS

Louis D. Bowman (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Louis D. Bowman
(Address) 805 Codell Road, Codell, Kansas 67663

SUBSCRIBED and SWORN TO before me this 17th day of January, 2007
Teresa M. Bowman My Commission Expires: 5-28-10
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

NOTARY PUBLIC - State of Kansas
TERESA M. BOWMAN
My Appt. Expires 5-28-10

PCT

