

**Notice:** Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117**

Form CP-4  
December 2003  
**Type or Print on this Form  
Form must be Signed  
All blanks must be Filled**

Lease Operator: Nadel and Gussman, L.L.C  
 Address: 15 E. 5th St., Suite 3200, Tulsa, OK 74103  
 Phone: (918) 583-3333 Operator License #: 32638  
 Type of Well: Gas Docket #: \_\_\_\_\_  
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
 The plugging proposal was approved on: 12/18/03 (Date)  
 by: Steve Durant (KCC District Agent's Name)  
 Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
 Producing Formation(s): List All (if needed attach another sheet)  
Topeka Depth to Top: 2936 Bottom: 3284 T.D. 3305'  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-129-10034-00-00  
 Lease Name: Dreyer  
 Well Number: 1-6  
 Spot Location (QQQQ): \_\_\_\_\_ - NW - NW - SE  
2310 Feet from  North /  South Section Line *KCC 1/24/07*  
2910 Feet from  East /  West Section Line *PCT per GPS*  
 Sec. 6 Twp. 32 S. R. 43  East  West  
 County: Morton  
 Date Well Completed: 1-21-55  
 Plugging Commenced: 12-20-03  
 Plugging Completed: 12-20-03

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Topeka	Gas	2936'	3284'	5-1/2"	3305'	750'
				8-5/8"	599'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP @ 2900' and dumped 2 sx cmt on plug. Cut off 5-1/2" csg @ 750' & pulled out. Pumped 70 sx cmt and could not fill to surface.  
Returned and tag TOC @ 740'. Pumped 50 sx plug. Top filled surface csg and cut off 6' below GL and welded on ID plate.

Name of Plugging Contractor: Eagle Well Service License #: NA 7407  
 Address: 1661 West 7th, Liberal, KS 67901

Name of Party Responsible for Plugging Fees: Nadel and Gussman, LLC  
 State of Oklahoma County, Tulsa, ss.

James R. Piland, Manager of Production (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) James Piland  
 (Address) 15 E. 5th St., Suite 3200, Tulsa, OK 74103

SUBSCRIBED and SWORN TO before me this 16th day of January, 20 07  
Kathy Carrow My Commission Expires: 8-1-07  
 Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

**RECEIVED**  
 KANSAS CORPORATION COMMISSION  
 JAN 22 2007  
 CONSERVATION DIVISION  
 WICHITA, KS