

15-163-01068-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rooks County. Sec. 6 Twp. 9S Rge. (E) 18 (W)
Location as "NE/CNW/SW" or footage from lines NW NW SW
Lease Owner Chief Drilling Co., Inc. - Kenneth Rupp
Lease Name GICK Well No. 1
Office Address Box 797 - Gt. Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 6/26 1964
Application for plugging filed 6/26 1964
Application for plugging approved 6/26 1964
Plugging commenced 6/26 1964
Plugging completed 6/26 1964
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty - Hays, Kansas
Producing formation Depth to top Bottom Total Depth of Well 3250 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	197	8-5/8"	197	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Wooden plug set @ 550'
Mixed 20 sacks cement through drill pipe
1/3 sack hulls & wooden plug set @ 180'
Mixed 20 sacks cement through drill pipe
1/3 sack hulls & wooden plug set @ 40'
Mixed 10 sacks cement through drill pipe

RECEIVED
STATE CORPORATION COMMISSION
6/29/64
JUN 29 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Chief Drilling Co., Inc.
Address Box 797 - Gt. Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
V. Richard Hoover (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *[Signature]* CHIEF DRILLING CO., INC.
Box 797 - Gt. Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 27th day of June, 1964

My commission expires Jan. 26, 1967

[Signature]
Carmen R. Cook, Notary Public.

15-163-01068-00-00

WELL LOG

Chief Drilling Co., Inc.
Box 797
Great Bend, Kansas

GICK #1
NW NW SW Sec. 6-9S-18W
Rooks County, Kansas

Kenneth Rupp
1035 Wichita Plaza
Wichita, Kansas

Commenced: 6/22/64
Completed: 6/26/64

RECEIVED
STATE CORPORATION COMMISSION
6/29/64
JUN 29 1964
CONSERVATION DIVISION
Wichita, Kansas

Contractor: Chief Drilling Co., Inc.

Casing Record: 8-5/8" @ 197' w/150 sacks Sunset & 2 sacks

DRY & ABANDONED

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Post Rock & Shale	0	155	2013 Gr.
Shale & Shells	155	920	2015 D.F.
Sand	920	1150	2018 K.B.
Shale & Shells	1150	1270	
Shale	1270	1426	
Anhydrite	1426	1463	
Shale	1463	1470	
Shale & Shells	1470	1885	
Shale & Lime	1885	2355	
Lime	2355	2490	
Shale & Lime	2490	2972	
Lime	2972	3184	
Lime & Shale	3184	3226	
Lime	3226	3250	
Total Depth	3250		

<u>FORMATION TOPS</u>	
Anhydrite	1426 + 592
Topeka	2972 - 954
Heebner	3184 - 1166
Toronto	3207 - 1189
Lansing	3226 - 1208

STATE OF KANSAS, COUNTY OF BARTON) SS

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the NW NW SW Sec. 6-9S-18W, Rooks County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

V. Richard Hoover
V. Richard Hoover, President

Subscribed and sworn to before me this 27th day of June, 1964.

Carmen R. Cook
Carmen R. Cook, Notary Public

My commission expires: Jan. 26, 1967.