


15-163-00135-00-00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Rooks County. Sec. 6 Twp. 9 Rge. 18 (E) (W) W

Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines C NE NW SE  
Lease Owner Jenkins-Ray Supply  
Lease Name W.J. Gilbert Well No. 2  
Office Address Box 967, Ponca City, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well  
Date well completed 2-6-48 19\_\_  
Application for plugging filed 3-25-66 19\_\_  
Application for plugging approved 3-28-66 19\_\_  
Plugging commenced 4-1-66 19\_\_  
Plugging completed 4-8-66 19\_\_  
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4	200	None
				6"	3519'	1210'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Dumped sand from 3519' to 3400' cemented from 3400' to 3386  
dumped cement to 3371' Set Bridge at 200' bailed hole and dumped 2 sacks  
cement. Cemented surface pipe with 4 yds redi-mix cement

RECEIVED  
STATE CORPORATION COMMISSION  
5/17/66  
MAY 17 1966

CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor Albert Leach (If additional description is necessary, use BACK of this sheet)  
Address Sterling Colorado

STATE OF Oklahoma COUNTY OF Kay, ss.  
W.J. Jenkins (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W.J. Jenkins Partner  
Box 967, Ponca City, Oklahoma (Address)

SUBSCRIBED AND SWORN to before me this 16th day of May, 19 66

My commission expires 8-3-67 Naomi Baker Notary Public.



6-9-18a

## CONTINENTAL OIL COMPANY

Gilbert #2

NE NW SE 6-9-18a

Described as your Gilbert Well No.2, located  
in Section 6, Township 9 South, Range 18 West  
Rooks, County, Kansas.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Sand & Shale	40	220
Shale & Shells	220	950
Sand	950	1180
Shale & Shells	1180	1220
Shale & Shells	1220	1457
Lime	1457	1477
Lime	1477	1495
Shale & Shells	1495	1723
Shale & Shells	1723	1935
Broken Lime	1935	2053
Broken Lime	2053	2300
Lime	2300	2365
Broken Lime	2365	2608
Lime	2608	2651
Broken Lime	2651	3038
Lime	3038	3456
Lime & Shale	3456	3490
Lime	3490	3497
Total depth	3497	

Expenses \$ 3535 with standard tools  
copy to book kept 3-2-18