

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: D.S. & W. Oil Operations
Address: P.O. Box 231, Claflin, KS 67525
Phone: (620) 587-3361 Operator License #: 6901
Type of Well: Oil Docket #: N/A
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) *(if SWD or ENHR)*
The plugging proposal was approved on: January 10, 2007 (Date)
by: Dave Wertz (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: 3262' Bottom: 3263' T.D. _____

Depth to Top: 3270' Bottom: 3271' T.D. _____

Depth to Top: 3279' Bottom: 3280' T.D. _____

API Number: 15-159-20,152-00-00
Lease Name: Rose Bieberle
Well Number: #2 NE
Spot Location (QQQQ): NE - SW - NE - KCC
3630 Feet from North / South Section Line PKT 1-29-07
1650 Feet from East / West Section Line per CP2/3
Sec. 20 Twp. 18 S. R. 10 East West
County: Rice
Date Well Completed: 10/08/1968
Plugging Commenced: 01/11/2007
Plugging Completed: 01/11/2007

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	0'	240'	10-3/4"	240'	0'
	Production	0'	3328'	5-1/2"	3328'	0'


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perforate at 900' and 1250' (4 shots each). Pump 35 sacks cement (60/40 Poz 4% gel) at 3200'. Pump 35 sacks cement at 1250'. Pump 35 sacks cement at 900'. Pull up to 290' and pump 160 sacks cement - circulated water but not cement to surface. Shut down for 1.5 hours - wait on cement. Pump 100 sacks cement - circulated to top on both sides. Shut in with 150# pressure. Rigged down and moved off.

Name of Plugging Contractor: D.S. & W. Well Servicing, Inc. License #: 6901
Address: P.O. Box 231, Claflin, KS 67525

Name of Party Responsible for Plugging Fees: D.S. & W. Oil Operations
State of Kansas County, Barton, ss.

Joseph F. Strube
(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


KAREN J. MITCHELL
Notary Public - State of Kansas
My Appt. Expires 04/13/2010

(Signature) Joseph F. Strube
(Address) P.O. Box 231, Claflin, KS 67525

SUBSCRIBED and SWORN TO before me this 12th day of January, 20 07

Karen J. Mitchell My Commission Expires: 4/13/2010
Notary Public

RECEIVED

JAN 24 2007

KCC WICHITA

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT