

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Bear Petroleum Inc.  
Address: Box 438 Haysville Ks. 67060  
Phone: (316) 524-1225 Operator License #: 4419  
Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 9-23-06 (Date)  
by: Duane Krueger (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Miss Depth to Top: 2804 Bottom: 2888 T.D. 2933  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-035-20739-00-00  
Lease Name: Weigle  
Well Number: 8 *KCC PKT-25-07 per CPA/3*  
Spot Location (QQQQ): \_\_\_\_\_ - SW SW NE  
2478 Feet from  North /  South Section Line  
2300 Feet from  East /  West Section Line  
Sec. 18 Twp. 31 S. R. 6  East  West  
County: Cowley  
Date Well Completed: \_\_\_\_\_  
Plugging Commenced: 9-02-06  
Plugging Completed: 10-9-06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	surface	surface	200	8 5/8	200	0
	Production	surf	2924	4 1/2	2924	1528

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

RIH CIBP set at 2532dump bailed 4 sacks cement on top. Sanded back to 2375' Dump bailed 6 sacks cement on top, Shot 4 1/2 casing at 1528' POH with 36 jts. of 4 1/2 RIH with tubing to 350' GenDor mixed and pumped 137 sacks of 60/40 poz with 4% gel to surface  
United cement ticket # 7036

RECEIVED  
KANSAS CORPORATION COMMISSION  
JAN 23 2007  
CONSERVATION DIVISION  
WICHITA, KS

Name of Plugging Contractor: Whiteman Ron dba Gen Dor Oil Co. License #: 9576  
Address: 8135 281st Rd Cambridge Ks. 67023

Name of Party Responsible for Plugging Fees: Bear Petroleum Inc.  
State of Kansas County, Sedgwick, ss.

R A Schremmer (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]  
(Address) Box 438 Haysville Ks. 67060

SUBSCRIBED and SWORN TO before me this 22nd day of January, 2007  
Shannon Howland My Commission Expires: 3/10/08  
Notary Public

SHANNON HOWLAND  
Notary Public - State of Kansas  
My Appt. Expires 3/10/08