

15-035-19436-00-00

Mr. H. H. Blair
First National Bank Bldg.
Winfield, Kansas

Re: Blair #8
SE SE NW, Sec. 11-30S -6E
Cowley County, Kansas

Dear Sir:

The following report covers facts pertinent to the drilling of your Blair #8 well. It includes geological tops as determined from sample analysis and correlated with drilling time log information, daily drilling depths, casing record, testing data, structural data, and sample description.

INFORMATION TOPS

<u>Formation</u>	<u>Depth</u>	<u>Sub-Sea Datum</u>
Hoover	1644	-185
Iatan	1811	-352
Stalnaker "A"	1832	-373
Total Depth	1837	-378

DAILY DRILLING DEPTH

<u>Date</u>	<u>Depth @ 8 A.M.</u>	<u>Footage Made Previous 24 Hrs.</u>
July 12, 1959	Move in	-0-
" 13, "	Start surface hole (set surface @ 2 P.M.)	201
" 14, "	201	268
" 15, "	469	691
" 16, "	1160	415
" 17, "	1575 (T.D. @ 10:04 P.M.)	262
" 18, "	1837 T.D.	

BIT RECORD

<u>No.</u>	<u>Size</u>	<u>Make</u>	<u>Type</u>	<u>Serial</u>	<u>Depth</u>		<u>Feet</u>	<u>Hrs.</u>
					<u>From</u>	<u>To</u>		
1	7-7/8	HTC	W7	R.T.	201	221	20	
2	"	HTC	OWV	R.T.	221	469	248	8
3	"	HTC	OSC	R.R.	469	1160	691	20 1/2
4	"	HTC	OSC	R.R.	1160	1534	374	22 1/2
5	"	HTC	OSC	R.T.	1534	1837	303	16 1/4

CASING RECORD

<u>Type</u>	<u>Footage</u>	<u>Size</u>	<u>Wt.</u>	<u>Thd.</u>	<u>Type</u>	<u>Set @</u>	<u>Cem. With</u>
Surface	205	8-5/8				201	125 sacks
Prod.	1832	4 1/2	14#	8 Rd.	Smls.	1832	100 sacks

15-035-19436-00-00

GEORGE R. McNEISH

GEOLOGICAL ENGINEER

524 STATE BANK BLDG.

WINFIELD, KANSAS



WELL:	Blair #8
LOCATION:	SE SE NW, Sec. 11-30S-6E Cowley County, Kansas
OPERATOR:	H. H. Blair
CONTRACTOR:	Watson Drilling Co.
DRILLING COMMENCED:	July 12, 1959
DRILLING COMPLETED:	July 18, 1959
PRODUCTION:	Oil
ELEVATION:	1459 KB 1457 DF 1454 GL
DATUM:	All measurements are taken from the rotary bushing, 5' above ground level.
ROTARY TOTAL DEPTH:	1837'