

L S Well Service, LLC
543A 22000 Road
Cherryvale, Kansas 67335
620-328-4433

DRILL LOG
JOHN GALEMORE

KCC of B
Timmons #10
19 814, T28, R15
Wilson Co, KS
API#15-205-26216-0000

| | | |
|-----------|--------------------|--|
| 0-5 | DIRT | 11-12-05 Drilled 11" hole and set 42' |
| 5-200 | SHALE | of 8 5/8" surface casing. Set with |
| 200-220 | LIME OIL | 10 sacks of Portland cement. |
| 220-300 | SHALE | |
| 300-310 | LIME | 11-14-05 Started drilling 6 3/4" hole |
| 310-330 | SHALE | |
| 330-440 | LIME | 11-14-05 Finished drilling to T.D. 1237' |
| 440-480 | SHALE | |
| 480-700 | LIME WITH SHALE | |
| 700-756 | SHALE | OIL ON PIT AT 210' |
| 756-758 | COAL | |
| 758-778 | LIME PINK | 661' 3" ON 3/4" ORIFICE |
| 778-780 | BLACK SHALE | 761' 4" ON 3/4" ORIFICE |
| 780-816 | SANDY SHALE | 786' 4" ON 3/4" ORIFICE |
| 816-832 | LIME OSWEGO | 836' 6" ON 3/4" ORIFICE |
| 832-836 | BLACK SHALE | 861' 25" ON 3/4" ORIFICE |
| 836-846 | LIME | 1037' 15" ON 3/4" ORIFICE |
| 846-850 | BLACK SHALE W/COAL | |
| 850-870 | SANDY SHALE | |
| 870-1060 | SHALE | |
| 1060-1061 | COAL | |
| 1061-1108 | SHALE | |
| 1108-1110 | BROWN SAND ODOR | |
| 1110-1114 | RED BED | |
| 1114-1172 | SANDY SHALE | |
| 1172-1237 | MISSISSIPPI | |

T.D. 1237'

RECEIVED
FEB 27 2006
KCC WICHITA