

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION**
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15-185-20,287-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 3-23-1971

Well Operator: Loewen Operator, Inc. KCC License #: 5631
(Owner / Company Name) (Operator's)

Address: P.O. Box 335 City: Canton

State: Kansas Zip Code: 67428 Contact Phone: (620) 628-4425

Lease: Estes Well #: 4 Sec. 5 Twp. 22 S. R. 14 East West

- NW - SE - NE Spot Location / QQQQ County: Stafford

1650 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

990 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8 Set at: 542' Cemented with: 300 Sacks

Production Casing Size: 5 1/2 Set at: 3880' Cemented with: 100 Sacks

List (ALL) Perforations and Bridgeplug Sets: Cast iron plug set between Arb. and Lans-K.C.

3586-88 3618-28 3872-75 3442

Elevation: 1945 G.L. / K.B. T.D.: 3880 P.B.T.D.: _____ Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): as per KCC rules and regulations.

930 50 570 50 40 10
Pipe recovery 1830

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: _____

Phone: () _____

Address: _____ City / State: _____

Plugging Contractor: Quality Well Service KCC License #: 31925
(Company Name) (Contractor's)

Address: 401 West Main, Lyons, Ks. 67554 Phone: (620) 727-3410

Proposed Date and Hour of Plugging (if known?): ASAP 10/31/06

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 5-25-2006 Authorized Operator / Agent: Maughan L. Foreman, P.E.
(Signature)

** Well already plugged - KCC-DIG*

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
DEC 05 2006
KCC WICHITA

Quality Well Service, Inc.

401 West Main
Lyons, KS 67554

Invoice

Date	Invoice #
11/6/2006	821

Bill To
Loewen Operator Inc. Box 335 Canton, KS 67428

P.O. No.	Terms	Lease Name
	net	Estes 4

Description	Qty	Rate	Amount
Rig Time	20.5	155.00	3,177.50T
Trucking Floor		100.00	100.00T
Sand		35.00	35.00T
Cement	5	9.00	45.00T
Shots	3	150.00	450.00T
Torch		50.00	50.00T
Water Truck	5	70.00	350.00T
Backhoe	3.5	70.00	245.00T
Phone Calls		15.00	15.00T
Clerical		20.00	20.00T
Wiping Rubber		20.00	20.00T
10-30-06 Drove to location, raised pole, checked hole, sanded off bottom, dug cellar, set floor, pulled slips, cut casing head off, checked hole, sand was at 3872', bailed 5 sacks cement with bailer, pulled stretch, had 18", ripped casing at 2240', worked pipe, ripped casing at 2010', worked pipe, swedge in, left on tension, drove home.			
10-31-06 Drove to location, pipe wasn't free, ripped casing at 1830', came free, pulled casing up to 930', pumped 15 gel, 50 sacks cement, pulled to 570', pumped 50 sacks, pulled to 40', pumped 15 sacks to surface, pulled joint, tore down floor and rig, cleaned up location.			
Subtotal			\$4,507.50
Sales Tax (6.3%)			\$283.97
Total			\$4,791.47

RECEIVED

DEC 05 2006

KCC WICHITA