

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION**
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
**This Form must be Typed
Form must be Signed
All blanks must be Filled**

API # 15 - 111-20417-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date _____.

Well Operator: Whiting Oil and Gas Corporation KCC License #: 4476
(Owner / Company Name) (Operator's)

Address: 1700 Broadway Suite 2300 City: Denver

State: Colorado Zip Code: 80290 Contact Phone: (303) 837 - 1661

Lease: Richmond Well #: 17-33 Sec. 17 Twp. 20 S. R. 13 East West

NW - SE - _____ - _____ Spot Location / QQQQ County: Lyon

1979 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

2007 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: EOR

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" 24# Set at: 208' Cemented with: 120 Sacks

Production Casing Size: 5 1/2" 15.50# Set at: 1958' Cemented with: 150 Sacks

List (ALL) Perforations and Bridgeplug Sets: N/A

Elevation: 1096' (G.L. / K.B.) T.D.: 1960' PBDT: 1916' Anhydrite Depth: N/A
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): The bottom plug is to be set 25' from PBDT if not perforated.

Middle plug is to be set 25' above the Douglas. Circulate to surface from 200' and put gel spacers between cement plugs.

If perforations are present place cement 50' below perfs and 50' above perfs.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Darrell Mahlock

Phone: (580) 661 - 3536

Address: Rt. 1 Box 177 City / State: Thomas, Oklahoma

Plugging Contractor: Hurricane Truck and Well Service KCC License #: 32006

Address: 3613 A Y Road, Madison KS 66860 Phone: (620) 437 - 2661
(Company Name) (Contractor's)

Proposed Date and Hour of Plugging (if known?): Not known 10-13-06 - 8:00 AM

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 9/06/2006 Authorized Operator / Agent: [Signature] (Kirk Love)
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202
* Well already plugged - KCC-DJ

**RECEIVED
SEP 08 2006
KCC WICHITA**

Dist
03