

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 169-20247-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date spd date 05/10/1984

Well Operator: Casebeer, Inc. KCC License #: 31934
(Owner / Company Name) (Operator's)

Address: 909 N. High Dr. City: McPherson

State: Kansas Zip Code: 67460 Contact Phone: (620) 242 - 7766

Lease: Johnson A Well #: 1-A Sec. 10 Twp. 16 S. R. 3 East West

SE4 - NE4 - SW4 Spot Location / QQQQ County: Salina

1650 1706 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

2310 2958 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" Set at: 340 Cemented with: 200 Sacks

Production Casing Size: 4 1/2" Set at: 3481 Cemented with: 150 Sacks

List (ALL) Perforations and Bridgeplug Sets: perfs from 3283 to 3293, Maquoketa dolomite was squeezed with 500 sacks of cement

Elevation: 1305 (G.L. / K.B.) T.D.: 3482 PBDT: _____ Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Well to be plugged according to the rules and regulations of the KCC

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? A copy of the scout card is included. There is no record of a log being taken. Silver Creek squeezed the Maquoketa dolomite with 500 sacks and cemented their packer and tubing in the process. We backed off 1500' tubing-most full of cement

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Mark Casebeer

Phone: (620) 242 - 7766

Address: 213 North Third City / State: Lindsborg KS 67456

Plugging Contractor: Quality Well Service KCC License #: 31925
(Company Name) (Contractor's)

Address: 401 W. Main, Lyons KS 67554 Phone: (620) 727 - 2410

Proposed Date and Hour of Plugging (if known?): When they can fit into schedule.

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 1/20/2007 Authorized Operator / Agent: Mark Casebeer
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202 **KCC WICHITA**

RECEIVED
JAN 24 2007

replacement card

SILVER CREEK OIL & GAS, INC.
WICHITA, KS 67203

10-16 -03W
SE NE SW

#1 "A" JOHNSON

site: 1/4 S & 1-3/4 W OF ASSARIA, KS
contr: H-30 DRILLING CO.
geol: H. C. HOPKINS

city: SALINE
field: OLSSON

API 15-169-20247

fr date 05/10/84 spd date 05/10/84 drig comp 05/16/84 card issued 01/03/85 last revised 12/30/87

ELV: 1305 KB LOG
tops.....depth/datum
MAQ.....3283 -1978
VIOLA.....3342 -2037
SIMP SH.....3437 -2132
RTD.....3482 -2177

IP status:
D & A, SIMP ,
CSG: 8-5/8" 340 / 200 SX, 4-1/2" 3481 / 150 SX
NO CORES OR DSTS
MICT - CO, PF (MAQ) 3283-3293, W / 4 SPF, AC 1000
GAL, FRAC 80,000 GAL W & 120,000# SD, NS, PROD
NON-COMMERCIAL, SQZ'D PFS W / 500 SX, P&A

INFO RELEASED: 12/30/87 - WAS D & A - TIGHT HOLE

COPYRIGHT 1987
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

RECEIVED
JAN 24 2007
KCC WICHITA

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Casebeer, Inc.
909 N. High Drive
McPherson, KS 67460

January 25, 2007

Re: JOHNSON #1-A
API 15-169-20247-00-00
SENE SW 10-16S-3W, 1706 FSL 2958 FEL
SALINE COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #2
3450 N. Rock Road, Suite 601
Wichita, KS 67226
(316) 630-4000

Sincerely



Barry Metz
Deputy Director