

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-03034-00-00  
Spot: SWSESW Sec/Twnshp/Rge: 17-16S-11W  
330 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: ALBERT OESER WEST Well #: 1  
County: BARTON Total Vertical Depth: 3330 feet

Operator License No.: 4252  
Op Name: KAHAN AND ASSOCIATES, INC  
Address: PO BOX 700780  
TULSA, OK 74170

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3329	1200	125 SX
SURF	8.625	280	0	175 SX

\$ 108.23

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/23/2007 9:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: DAVID M. WILSON Company: KAHAN AND ASSOCIATES, INC. Phone: (918) 492-9797

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 10% gel - 400# hulls.  
Pull 1200' casing.  
Plug through casing.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/23/2007 12:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Cut casing at 1500' - pumped 85 sxs cement with 150# hulls.  
Pulled casing to 1100' - pumped 40 sxs cement with 100# hulls.  
Pulled all casing and topped off with 100 sxs cement with 150# hulls.

Perfs:

Top	Bot	Thru	Comments
3195	3202		
3158	3166		
3095	3101		
3082	3086		
2948	2954		

**INVOICED**

DATE 1-31-07  
INV. NO. 2007061279

Remarks: ALLIED CEMENTING COMPANY-TICKET #031411.

Plugged through: CSG

District: 04

Signed

*Marvin Mills*

(TECHNICIAN) **RECEIVED**

**JAN 29 2007**

Form CP-2/3

**KCC WICHITA**

**JAN 24 2007**

*PKT*

Kahan & Associates, Inc. 15-009-03034-00-00 17-16-11W  
 CLARK KNIGHT DRILG CO #1 OESER SW SE SW

Contr. ARI-KAN DRILG BARTON County

E. 1877RB Comm. 9-2-58 Comp. 10-10-58 IP 80 BOPD

Tops	Depth	Datum
KC	3015	-1138
CONG	3300	-1423
ARB	3325	-1448
TD	3330	-1453

Casing  
 8" 280 w 175 x 5  
 5" 3329 w 125 x 5  
 CO: PERF 3195-3202: ACID 500  
 PB 3184: PERF 3158-65: ACID  
 500: SWB 2 1/2 BOPH, NW

KRAFT PRUSA POOL


Toply 1-22-07

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS