

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-20297-00-00  
Spot: E2E2SW Sec/Twnshp/Rge: 24-14S-11W  
1320 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: SEBESTA Well #: 2  
County: RUSSELL Total Vertical Depth: 3195 feet

Operator License No.: 9408  
Op Name: TRANS PACIFIC OIL CORPORATION  
Address: 100 SOUTH MAIN STE 200  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2705		
PROD	5.5	2950	0	225 SX
SURF	8.625	252	0	225 SX

\$ 103.84

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/22/2007 10:00 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: FRANK BIEKER Company: TRANS PACIFIC OIL CORPORATIO Phone: (785) 658-7258

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 10% gel - 500# hulls - 11 sxs gel.  
Casing leak 300'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/22/2007 12:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

RIH with tubing to 2680'.  
Rigged to tubing - pumped 11 sxs gel - followed with 15 sxs 60/40 pozmix with 350# hulls mixed in.  
Pulled tubing to 1500'  
Rigged to tubing - pumped 115 sxs 60/40 pozmix with 150# hulls mixed in to circulate cement out of 5 1/2" casing.  
Shut in 5 1/2" casing - pumped 10 sxs 60/40 pozmix to circulate cement up 8 5/8" annulus.  
Pulled tubing - topped off 5 1/2" casing with 15 sxs.  
Hole standing full.

Perfs:

Top	Bot	Thru	Comments
2870	2872		
2808	2826		

**INVOICED**  
DATE 1-31-07  
INV. NO. 2007061288

**RECEIVED**

**JAN 29 2007**

**KCC WICHITA**

Remarks: ALLIED CEMENTING COMPANY-TICKET #32990.

Plugged through: TBG

District: 04

Signed [Signature]  
(TECHNICIAN)

JAN 23 2007

PKT

W. P. ASH & AMERICAN DRLG. CO. #2 SEBESTA 24-14-11W  
 WICHITA, KANSAS C E2 E2 SW  
 Contr. AMERICAN DRLG. CO., LTD Cty. RUSSELL  
 Geol. CHAS. KING Pool WILSON CREEK EXT

E. 1681 KB Cm. 2/20/69 Cp. 4/24/69 IP PMP 65 BOPD, NW/  
 LANS 2808-26  
 API 15-167-20,297 2870-72 GR 39.2

SMP	Tops	Depth	Datum
	HOW	2357	- 676
	TOP	2434	- 753
	HEEB	2682	-1001
	BR LM	2772	-1091
	LANS	2787	-1106
	BKC	3121	-1440
	CONG	3144	-1463
	ARB	3181	-1500
	ID	3195	-1514

Csg. 8" 252/225 sx 5 1/2" 2950/225 sx  
 DST 2430-50/90", 310' GIP, 60' GCM, BHP  
 134-134#/30", FP 48-67#  
 DST 2808-29/1', 120' VHOCM, 100' CLN GSY  
 OIL, BHP 694-694#/30", FP 47-96#  
 DST 2806-29/1', 1500' GIP, 40' OCM, 60'  
 VHO&GCM, 120' GO, BHP 694-694#/30",  
 FP 48-96#  
 DST 2860-80/1', 210' HOCM, BHP 732-739#/30"  
 FP 86-115#  
 PF /2870-72, MA 250, SWB LD & SWB 36 BO &  
 46 BBLS/6 HRS, SET BRIDGE PLUG AT 2850,  
 PF /2808-26, MA 500, SWB LD & SWB 23 BOPH  
 400' OB, A 3000, PMP 87-112 BOPD, AVG  
 94 BOPD

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS