

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-22400-00-00
Spot: SESW Sec/Twnshp/Rge: 29-15S-12W
660 feet from S Section Line, 3300 feet from E Section Line
Lease Name: LUERMEN-PALSER Well #: 1
County: RUSSELL Total Vertical Depth: 3342 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 SOUTH MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3337	0	150 SX CMT
SURF	8.625	471	0	225 SX CMT

108.62

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/23/2007 10:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: FRANK BIEKER Company: TRANS PACIFIC OIL CORPORATIO Phone: (785) 658-7258

Proposed Plugging Method: Ordered 335 sxs 60/40 pozmix - 10% gel - 500# hulls.
Dakota 172' - 447'. Anhy. 814' - 834'. Salt 1216' - 1486'.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/23/2007 12:10 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Express Well Service dug out backside of 8 5/8" - removed bull plug - found backside to be full of cement - visual checked.
LK Wireline shot a three SPF at 1525' and 825'.
RIH with tubing to 2400'. Rigged to tubing and pumped 100 sxs 60/40 pozmix with 300# hulls mixed in.
Pulled tubing to 1500'. Rigged to tubing and pumped 80 sxs with 200# hulls to circulate cement into pit.
Pulled tubing. Rigged to 5 1/2" with a swedge and pumped 30 sxs 60/40 pozmix.
Max. P.S.I. 600#. S.I.P. 250#.

Perfs:

Top	Bot	Thru	Comments
3337	3342	OH	

INVOICED
DATE 1-31-07
INV. NO. 2007061288

RECEIVED
JAN 29 2007

Remarks: ALLIED CEMENTING COMPANY-TICKET #32991.

KCC WICHITA

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

JAN 23 2007


REPLACEMENT CARD

NATIONAL DEVELOPMENT COMPANY 29-15-12W
 205 E. CENTRAL, #120 #1 LUERMEN-PALSER C SE SW
 WICHITA, KS. 67202

CONTR DUKE DRILLING CO., INC. CTY RUSSELL

GEOL RAY PALMER FIELD HALL-GURNEY

ELV 1877 KB SPD 6/21/84 CARD ISSUED 4/4/85 IP P 75 BOPD, NW
 1872 GL DRLG COMP 6/26/84 ARB OH 3337-3342
 API 15-167-22,400-00-00



SMP	Tops	Depth/Datum
ANH	814+1063
HOW	2653- 776
SEV	2676- 799
TOP	2690- 813
HEEB	2970-1093
TOR	2988-1111
DOUG	3001-1124
BR LM	3056-1179
KC	3066-1189
BKC	3262-1385
CONG	3307-1430
ARB	3336-1459
RTD	3342-1465

8 5/8 " 471 / 225SX, 5 1/2 " 3337 / 150SX
 DST (1) 3305-3342 (CONG) / MISRUN
 DST (2) 3305-3342 (CONG) / 30-30-30-30, (1ST OP) SB THRU-
 OUT, (2ND OP) SB THRU-OUT, REC 200' SLI MDY OIL, 1600' CL
 GSY OIL, SIP 1027-1018#, FP 209-465 / 562-673#, HP 1794-
 1782#
 MICT - CO, (ARB OH), SWB DWN, GSO, NAT, POP, P 75 BOPD,
 NW, 7/13/84

INFO RELEASED: 12/12/85 - WAS OIL WELL - TIGHT HOLE
NOTE: 4/4/85 - ORIGINALLY FIRST REPORTED AS LUERMAN-
 PALFER