

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-22570-00-00
Spot: NESESW Sec/Twnshp/Rge: 29-15S-12W
990 feet from S Section Line, 2970 feet from E Section Line
Lease Name: LUERMAN Well #: 2
County: RUSSELL Total Vertical Depth: 3500 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 SOUTH MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3405	0	125 SX CMT
SURF	8.625	454	0	200 SX CMT

\$ 113.75

Well Type: SWD UIC Docket No: D23916.0 Date/Time to Plug: 01/23/2007 12:30 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: FRANK BIEKER Company: TRANS PACIFIC OIL CORPORATIO Phone: (785) 658-7258

Proposed Plugging Method: Ordered 325 sxs 60/40 pozmix - 10% gel - 500# hulls.
Dakota 169' - 444'. Anhy 811' - 831'. Salt 1213' - 1483'

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/23/2007 1:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

LK Wireline shot a three SPF at 1525' - 825' - 200'.
Allied rigged to 5 1/2" casing with a swedge - pumped 325 sxs 60/40 pozmix with 500# hulls mixed in.
Max. P.S.I. 500#. S.I.P. 200#.
Pulled bull plug off backside of 8 5/8" casing.
Hole standing full of cement.

Perfs:

Top	Bot	Thru	Comments
3416	3500		OH

INVOICED
DATE 1-31-07
INV. NO. 2007061288

RECEIVED
JAN 29 2007
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #32992.


Plugged through: CSG

District: 04

Signed [Signature]
(TECHNICIAN)

JAN 23 2007

NATIONAL DEVELOPMENT COMPANY
 205 F. CENTRAL, #120 #2 LUERMAN 29-15-12W
 WICHITA, KS 67202 NE SE SW
 CONTR DUKE DRILLING CO. CTY RUSSELL
 GEOL ROD TREMBLAY FIELD HALL-GURNEY



ELV 1874 KB SPD 3/14/85 CARD ISSUED 8/22/85 IP SWDW
 1866 GL DRLG COMP 3/21/85 ARB 3416-3500

SMP	Tops	Depth/Datum
GR HAVEN	2378-	504
TARK	2452-	578
HOW	2659-	785
SEV	2677-	803
TOP	2693-	819
HEEB	2970-	1096
TOR	2988-	1114
DOUG	3002-	1128
BR LM	3058-	1184
LANS	3066-	1192
BKC	3260-	1386
ARB	3355-	1481
RTD	3500-	1626

API 15-167-22,570-00-00
 8 5/8 " 454 / 200SX, 5 1/2 " 3405 / 125SX
 NO CORES OR DST'S
 MICT - CO, PF (ARB) 3416-3500, AC 750G (REG), SWB DWN,
 SWDW - INJECTION RATE SATISFACTORY

NOTE: CORRECTION: 3/28/85 - ORIGINALLY FIRST REPORTED IN
 C E/2 E/2 SW