

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-02198-00-00
Spot: NWNWSWSE Sec/Twnshp/Rge: 15-24S-18E
1265 feet from S Section Line, 2600 feet from E Section Line
Lease Name: BOWLUS A Well #: 9N
County: ALLEN Total Vertical Depth: 893 feet

Operator License No.: 32851 •
Op Name: L & G PETROLEUM OPERATING, LLC
Address: 1000 CAMINO DEL OESTE
BAKERSFIELD, CA 93309

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| PROD | 2.375 | 895 | 0 | |
| SURF | 8.25 | 15 | 0 | |

\$ 35

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/21/2006 12:30 PM
Plug Co. License No.: 31440 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC
Proposal Rcvd. from: RANDY STANLEY Company: L&G PETROLIUM OPER., LLC Phone: (620) 365-7435

Proposed Plugging Method: RUN 1 INCH PIPE TO 875 FT / CEMENT TO SURFACE. THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 893' THAT HAD BEEN CEMENTED IN AT TD ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT INSIDE AND OUTSIDE THE 2" CASING.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/21/2006 2:30 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

Perfs:

1" PIPE WAS RAN INTO THE 2" CASING TO 875'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. 1" PIPE WAS WASHED INTO 2" AND 15" ANNULUS TO 450'. AT THAT DEPTH A SOLID OBSTRUCTION WAS ENCOUNTERED. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

RECEIVED
KCC DISTRICT #3

JAN 24 2007 CPT

CHANUTE, KS

INVOICED

DATE 1-31-07

INV. NO. 2007061280

Remarks:

Plugged through: TBG

District: 03

Signed

Clayton P. Titel

(TECHNICIAN)

RECEIVED Form CP-2/3

JAN 25 2007

KCC WICHITA

AKG