

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-21366-00-01
Spot: SESENE Sec/Twnshp/Rge: 9-24S-18E
3052 feet from S Section Line, 165 feet from E Section Line
Lease Name: WEST RIGGS Well #: 19
County: ALLEN Total Vertical Depth: 1002 feet

Operator License No.: 32851
Op Name: L & G PETROLEUM OPERATING, LLC
Address: 1000 CAMINO DEL OESTE
BAKERSFIELD, CA 93309

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1002	0	
SURF	8.625	20	0	

\$ 35

Well Type: EOR UIC Docket No: E19268.1 Date/Time to Plug: 12/21/2006 10:30 AM
Plug Co. License No.: 31440 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC
Proposal Rcvd. from: RANDY STANLEY Company: L&G PETROLIUM OPER.,LLC Phone: (620) 365-7435

Proposed Plugging Method: SPOT COTTON SEED HULLS AND GEL ON BOTTOM TO 965', LET SET OVERNIGHT, RUN 2" TO 965' CEMENT TO TOP. THIS WELL CONSISTED OF 4 1/2" CASING TO 1002' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO CIRCULATE THE 4 1/2" CASING FULL OF CEMENT.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/21/2006 12:30 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

2" PIPE WAS RAN INTO THE 4 1/2" CASING TO 938'. 4 BARRELS OF GEL AND COTTON SEED HULLS WERE PUMPED INTO THE 2" TUBING TO APREVENT SETTLAGE. CEMENT WAS PUMPED INTO THE 2" TUBING UNTIL CEMENT CIRCULATED FROM THE 4 1/2" CASING AT SURFACE. THE 2' TUBING WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

Perfs:

Top	Bot	Thru	Comments
968	998		

RECEIVED
KCC DISTRICT #3

JAN 24 2007 CPT

CHANUTE, KS

INVOICED

DATE 1-31-07

INV. NO. 2007061280

Remarks:

Plugged through: TBG

District: 03

Signed

Clayton P. Titel
(TECHNICIAN)

RECEIVED

Form CP-2/3

JAN 29 2007

KCC WICHITA

PST