

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-101-21992-00-00  
Spot: N2N2SW Sec/Twnshp/Rge: 32-18S-29W  
2310 feet from S Section Line, 1320 feet from W Section Line  
Lease Name: EHMKE AF Well #: 1  
County: LANE Total Vertical Depth: 4700 feet

Operator License No.: 3988  
Op Name: SLAWSON EXPLORATION COMPANY,  
Address: 204 N ROBINSON, STE 2300  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	215		

\$ 152.75

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/08/2007 4:00 PM

Plug Co. License No.: 5147 Plug Co. Name: BEREDCO, INC.

Proposal Rcvd. from: STEVE SLAWSON Company: SLAWSON EXPLORATION Phone: (405) 232-0201

Proposed Plugging Method: 1ST PLUG AT 2220' WITH 50 SX CMT. 2ND PLUG AT 1380' WITH 80 SX CMT. 3RD PLUG AT 640' WITH 40 SX CMT. 4TH PLUG AT 240' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON

WitnessType: NONE

Date/Time Plugging Completed: 01/08/2007 6:00 PM

KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

Perfs:

1ST PLUG AT 2220' WITH 50 SX CMT. 2ND PLUG AT 1380' WITH 80 SX CMT. 3RD PLUG AT 640' WITH 40 SX CMT. 4TH PLUG AT 240' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

RECEIVED  
KANSAS CORPORATION COMMISSION  
JAN 26 2007  
CONSERVATION DIVISION  
WICHITA, KS


INVOICED

DATE 1-31-07  
INV. NO. 2007061284

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01



Signed

Jerry W. Stapleton PART II  
(TECHNICIAN)

Form CP-2/3