

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-22257-00-00
Spot: N2SESE Sec/Twnshp/Rge: 21-27S-11W
854 feet from S Section Line, 765 feet from E Section Line
Lease Name: HAMMEKE Well #: 1
County: PRATT Total Vertical Depth: 4425 feet

Operator License No.: 3959
Op Name: SIROKY OIL MANAGEMENT
Address: PO BOX 464
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	735		WITH 375 SX CMT

\$ 143.81

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/19/2007 9:00 PM
Plug Co. License No.: 33610 Plug Co. Name: FOSSIL DRILLING, INC.
Proposal Rcvd. from: SCOTT ALBERG Company: FOSSIL DRILLING, INC. Phone: (620) 672-5778

Proposed Plugging Method: IST PLUG AT 760' WITH 50 SX CMT. 2ND PLUG AT 300' WITH 40 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: NONE
Date/Time Plugging Completed: 01/19/2007 11:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:
IST PLUG AT 760' WITH 50 SX CMT. 2ND PLUG AT 300' WITH 40 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. NO MOUSE HOLE.

Perfs:

INVOICED
DATE 1-31-07
INV. NO. 2007061285

Remarks: USED 60/40 POZMIX 6% GEL BY JET STAR.
Plugged through: DP

District: 01 Signed Stephen J. Pfeifer
(TECHNICIAN)

