

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-19106-00-00  
Spot: SESENW Sec/Twnshp/Rge: 20-16S-11W  
2970 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: PETER SCHMITT B Well #: 1  
County: BARTON Total Vertical Depth: 3304 feet

Operator License No.: 4252  
Op Name: KAHAN AND ASSOCIATES, INC  
Address: PO BOX 700780  
TULSA, OK 74170

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3300	0	w/125 sxs cmt
SURF	8.625	208	0	w/unknown sxs cmt

\$107.38

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/29/2007 9:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 500# hulls.  
CIBP at 3230'.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/29/2007 10:30 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Sanded off bottom to 2900' and topped with 5 sxs cement.  
Rigged to casing - pulled 1" stretch casing - parted 2-3 joints down.  
Cut holes in casing at 1495' and 775'.  
RIH with tubing - rigged to tubing - pumped 145 sxs 60/40 pozmix - 10% gel with 250# hulls mixed into circulate cement to surface.  
POOH. Pulled tubing - topped 5 1/2" casing with 15 sxs cement.  
Hole standing full of cement.

Perfs:

Top	Bot	Thru	Comments
3230			
3210	3214		
3188	3198		
3170	3176		
3099	3103		
2957	2965		

INVOICED

DATE 2-1-07

INV. NO. 2007061292

Remarks: COPELAND ACID & CEMENTING COMPANY-TICKET #031506.

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

RECEIVED

Form CP-2/3

JAN 31 2007

KCC WICHITA

JAN 29 2007

pet

HARMS & KNIGHT

#1

SCHMITT

20-16-11W  
SE SE NW

Contr.

BARTON

Coun

E 1869

Comm.

Comp.

1-19-51

IP


43 BOPD

Tops	Depth	Datum
DOUG	2949	-1080
LANS	3002	-1133
ARB	3299	-1430
T.D.	3304	-1441

Casing

8" 208 3 BOPD  
5" 3300

KRAFT-PRUSA POOL



INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS