

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-23074-00-00
Spot: SWNE Sec/Twnshp/Rge: 18-10S-19W
4289 feet from S Section Line, 1056 feet from E Section Line
Lease Name: ANDERSON Well #: 12
County: ROOKS Total Vertical Depth: 4041 feet

Operator License No.: 5214
Op Name: LARIO OIL & GAS COMPANY
Address: 301 SOUTH MARKET STREET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4040	0	w/800 sxs cmt
SURF	8.625	212	0	w/140 sxs cmt

\$ 131.33

Well Type: SWD UIC Docket No: D25778.0 Date/Time to Plug: 01/25/2007 9:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: TOM BERENS Company: LARIO OIL & GAS COMPANY Phone: (785) 625-5023

Proposed Plugging Method: Ordered out 350 sxs 60/40 pozmix - 10% gel - 600# hulls.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/25/2007 11:00 AM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Swaged onto 5 1/2" - mixed and pumped 340 sxs cement with 600# hulls.
Max. P.S.I. 500#. S.I.P. 250#.
Hooked up to the 8 5/8" and pumped 10 sxs cement.
S.I.P. 500#.

Perfs:


INVOICED
DATE 2-1-07
INV. NO. 2007061293

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed



(TECHNICIAN)



RECEIVED Form CP-2/3

JAN 31 2007

KCC WICHITA



JAN 29 2007

STATE KANS COUNTY ROOKS
FIELD MARCOTTE (MULTIPAY)
OPER PRICE ROBERT R OPERATING
WELL 12 ANDERSON
API 15-163-23074-0000
SPUD 01/09/1990
DTD 4041 LTD FTD ARBUCKLE
LOC

WELL CLASS 4290FSL
STATUS U
COMP SERVICE 02/17/1990
PBTD

18-10S-19W
SW NE NE
915FEL SEC



Petroleum Information

KS 6-030690

IP SALT WATER DISPOSAL WELL
INJ ZONE: ARBUCKLE 3960-3980
FIRST REPORT & COMPLETION

CSGS: 8 5/8 @ 212 W/ 140 SACKS
5 1/2 @ 4040 W/ 800 SACKS

DRLG COMP 1/16/90 RIG REL 1/16/90

PERFS: ARBUCKLE PERF W/ 1/FT 3960-3980
ACID 1000 GALS 15% HCL

NO CORES

EL: 2217 KB 2212 GR

LOG TOPS:
STONE CORRAL 1634 +583
BSE STN CORRAL 1668 +549
TOPEKA 3216 -999
HEEBNER 3423 -1206
TORONTO 3447 -1230
LANSING 3463 -1246
BSE KANSAS CITY 3694 -1477
PENN CONGL 3704 -1487
PENN CONGL SD 3766 -1549
ARBUCKLE 3780 -1563
TD 4041 -1824

OPER ADDRESS: BOX 470442, TULSA, OK 74147

CONTR: RED TIGER DRLG GEOL: ROBERT R PRICE

KS 6-030690

Copyright 1990 Petroleum Information Corporation